

APR 1 4 2005

PUBLIC SHAVICE COMMISSION

COMMONWEALTH OF KENTUCKY

BEFORE THE PUBLIC SERVICE COMMISSION

In Matter of:

AN ASSESSMENT OF)
KENTUCKY'S ELECTIRC) ADMINISTRATIVE
GENERATION, TRANSMISSION) CASE NO. 2005-00090
AND DISTRIBUTION NEEDS)

RESPONSE TO ORDER FOR INFORMATION

DATED MARCH 10, 2005

CASE NO. 2005-00090

SHELBY ENERGY COOPERATIVE, INC.

Witnesses who will be available to respond to questions concerning the information requested:

Dudley Bottom, Jr., President & CEO

Don Turner, Senior Vice-President of Operations

Wayne Anderson, Vice-President of Plant Engineering & Technology

1. Provide a summary description of your utility's resource planning process. This should include a discussion of generation, transmission, demand-side, and distribution resource planning.

Shelby Energy Cooperative (Shelby Energy) prepares a Twenty-Year Power requirements Study in association with East Kentucky Power Cooperative (EKPC) every two years. This demand-side study provides the basis for Shelby Energy's distribution planning process.

The consumer and electrical loading projections from the Power Requirements Study are the input for the Long Range System Plan. This plan develops the distribution system model that will serve new plant additions, uprating of existing plant, and a scheduled replacement of the distribution system.

Two or Four Year Work Plans are developed to provide for system growth and modification involving specific projects with detailed cost estimates and current system needs.

The entire planning process is subject to Rural Utilites Service (RUS) input and approval.

Exhibit A, pages (1) through (10) provide an overview of the planning process.

East Kentucky Power Cooperative is responding on behalf of Shelby Energy Cooperative concerning the generation and transmission.

Introduction Executive Summary

Shelby Energy Cooperative, Inc., (Shelby Energy), located in Shelbyville, Kentucky, oad forecast report contains Shelby Energy's long-range forecast of energy and s an electric distribution cooperative that serves members in ten counties. This jeak demand.

service area industrial development, electric price, household income, weather, and Shelby Energy and its power supplier, East Kentucky Power Cooperative (EKPC), worked jointly to prepare the load forecast. Factors considered in preparing the orecast include the national and local economy, population and housing trends, appliance efficiency changes.

EKPC prepared a preliminary load forecast, which was reviewed by Shelby Energy for reasonability. Final projections reflect a rigorous analysis of historical data combined with the experience and judgment of the manager and staff of Shelby Energy. Key assumptions are reported beginning on page 22.

2

Executive Summary (continued)

THE REAL PROPERTY.

both parties' needs. Shelby Energy uses the forecast in developing two-year work areas of marketing analysis, transmission planning, generation planning, demandplans, long-range work plans, and financial forecasts. EKPC uses the forecast in EKPC and Shelby Energy. Cooperation helps to ensure that the forecast meets The load forecast is prepared biannually as part of the overall planning cycle at side planning, and financial forecasting. The complete load forecast for Shelby Energy is reported in Table 1-1. Residential and commercial sales, total purchases, winter and summer peak demands, and load factor are presented for the years 1990 through 2024.

8

Table 1-1 (Continued) Tabl	是一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个	etabl						
Season South Sou		27		E.	able 1-1 (co	ontinued		
Noncoincident Peark Demand (MIV) Purchased Power Segsish While Year Summer Year (MVIII) 1980 - 91 45.9 1991 45.3 1991 230,097 1990 - 91 45.9 1991 45.3 1991 230,097 1992 - 91 33.5 1992 46.8 1994 289,280 203,097 1992 - 91 33.5 1993 45.3 1994 289,280 203,097				L ~21	oy Energy	Coopera	tive	
Seasch S. Winter Year Summer Year (MWI) 1980 39.4 1991 230,097 1992 39.4 1991 230,097 1992 39.4 1991 230,097 1992 39.4 1991 230,097 1992 39.4 1992 39.4 1992 230,097 1992 39.4 1993 241,237 1992 39.5 316,629 39.4 39.5 39.5 39.4 39.5				004 Loa	d Forecast	Peaks S	ummary	
Season Season Season Summer Year Summer Year Summer Year Summer Year Summer Year Summer Year Summer Sao, 1991 203,097 1991 - 203,097 1991 - 203,097 1991 - 203,097 1991 - 203,097 1991 - 203,097 1992 - 93 313,31 1992 - 93 313,31 1992 - 93 313,31 1992 - 93 313,31 1992 - 93 313,31 1995 - 93 313,31 1995 - 93 313,31 1995 - 93 313,31 1995 - 93 313,31 1995 - 93 313,31 1995 - 93 313,31 1995 - 93 313,31 1996 - 93 313,32 1996 - 93 313,32		Nov	icoincident Pe	eak Demar	id (MFP)	Purcl	insed Power	Load Factor
1980 - 90 45.4 1990 39.4 1990 203,097 1990 - 91 45.9 1991 45.3 1991 201,197 1990 - 91 45.9 1992 241,237 241,237 1990 - 91 51.3 1993 51.4 1992 241,237 1992 - 94 51.8 1994 280,280 1994 280,280 1994 - 95 77.2 1995 66.4 1997 344,483 1996 - 96 75.4 1996 313,011 344,483 1996 - 97 75.4 1998 76.9 1997 344,483 1996 - 98 75.4 1998 76.9 1996 344,483 1996 - 99 80.9 1999, 76.9 78.4 2000 413,500 1997 - 98 75.4 1998 76.9 1996 384,630 1996 - 90 80.1 1950 78.8 2000 412,100 2000 - 10 96.1 2001 81.3 2001 412,100 <t< th=""><th></th><th>Season</th><th>Winter</th><th>Year</th><th>Summer</th><th>Year</th><th>(MWh)</th><th>(%)</th></t<>		Season	Winter	Year	Summer	Year	(MWh)	(%)
1990 - 91 45.9 1991 45.3 1991 230,197 1991 - 92 51.3 1992 46.8 1992 241,277 1992 - 93 51.3 1993 62,1 1993 241,277 1992 - 93 51.3 1993 62,1 1993 241,277 1994 - 95 71.2 1995 62,1 1995 316,629 1995 - 96 63.8 1994 60.8 1994 289,280 1995 - 96 63.8 1994 60.8 1995 316,629 1995 - 97 60.2 1995 62,1 1995 313,011 1995 - 97 60.2 1995 62,1 1995 313,011 1995 - 97 60.2 1996 63.0 1996 313,011 1995 - 97 83.1 2000 81.8 2000 412,170 1995 - 97 83.1 2000 81.8 2000 412,170 2000 - 01 96.5 2004 81.3 2003 415,74 2001 - 03 61.1 2005 81.8 2000 455,74 2004 - 05 103.1 2005 81.8 2005 456,742 2007 - 06 115.6 2009 103.5 2005 456,742 2007 - 06 115.6 2009 103.5 2005 537,112 2008 - 09 121.2 2009 103.5 2009 537,112 2008 - 09 121.2 2009 103.5 2004 460,160 2007 - 10 124.6 2010 108.4 2011 532,175 2011 - 12 131.4 2012 118.5 2012 610,681 2012 - 13 136.3 2013 115.0 2015 610,681 2012 - 13 14.7 2014 118.5 2015 610,681 2015 - 16 143.1 2016 125.0 2015 610,74 2016 - 17 134.4 2017 129.3 2015 610,74 2017 - 18 155.7 2018 133.5 2019 845,340 2017 - 18 155.7 2018 133.5 2019 845,340 2017 - 18 155.7 2011 147.2 2021 845,340 2017 - 2022 18.6 2022 151.2 2017 - 2022 18.6 2023 151.2 2017 - 2022 18.6 2023 151.2 2017 - 2022 151.2 2022 151.2 2017 - 2022 151.2 2022 142.5 2017 - 2022 151.2 2022 151.2 2017 - 2022 142.5 2023 2032 2032 2017 - 2022 2032 2032 2032 2032 2032 - 2032 2032 2033 2033 2032 - 2032 2033 2033 2033 2032 - 2032 2033 2033 2033 2033 - 2033 2033 2033 2033 2035 - 2035 2035 2035 2035 2035 - 2035 2035 2035 2035 2035 - 2035 2035 203		1989 - 90	1	1990	39.4	1990	203,097	\$1.1%
191 - 22 51.3 1992 46.8 1992 241.237 1922 - 93 53.5 1993 51.4 1993 266,114 1932 - 94 63.8 1994 60.8 1995 266,114 1935 - 56 77.2 1995 62.0 1995 313,011 1996 - 97 77.3 1996 313,011 313,011 313,011 1996 - 97 66.2 1997 66.4 1997 344,483 1996 - 97 69.2 1997 66.4 1997 344,483 1997 - 98 73.4 1998 384,630 363,461 1999 - 90 85.0 2000 412,170 364,483 2000 - 01 95.1 2000 81.8 2001 413,690 2000 - 02 85.0 2002 81.8 2001 413,690 2000 - 03 96.1 2002 81.3 2002 435,248 2000 - 04 107.1 2003 81.3 2002 445,248	•	16 - 0661	45.9	1661	45.3	1661	230,197	57.3%
1992 - 93 51.4 1993 266,114 1993 - 94 63.8 1994 60.8 1994 289,280 1993 - 95 77.2 1995 60.4 1996 313,011 1995 - 56 77.3 1996 313,011 313,011 1995 - 56 77.4 1998 75.4 1996 313,011 1996 - 97 75.4 1998 75.4 1998 44,483 1997 - 98 75.4 1998 75.3 1996 34,483 1997 - 98 75.4 1998 75.4 1998 36,1461 1998 - 90 88.1 70.0 1999 384,630 36,1461 2000 - 01 85.0 1999 78,483 2000 446,483 2000 - 01 85.0 2001 81.8 2000 446,148 2000 - 01 85.0 2003 81.3 2002 446,483 2001 - 02 85.0 2003 81.3 2003 446,483 2004 - 03		1991 - 92	51.3	1992	46.8	1992	241,237	53.7%
1993 - 94 61.8 1994 66.8 1994 289,280 1994 - 95 77.2 1995 62,1 1995 316,629 1996 - 95 77.2 1996 66,4 1997 313,011 1996 - 97 66.2 1997 66,4 1997 313,011 1996 - 98 75.4 1998 75.4 1998 36,461 1997 - 88 77.4 1998 76.9 1999 384,630 1999 - 60 85.1 2000 78.4 2000 412,170 2000 - 01 95.1 2001 81.8 2000 415,380 2000 - 02 85.0 2002 81.3 2003 445,432 2000 - 03 96.1 2002 81.3 2003 460,160 2000 - 04 96.5 2002 88.5 2003 476,742 2000 - 05 10.1 2005 88.5 2003 476,742 2004 - 05 10.1 2005 91.8 2003 4		1992 - 93	53.5	1993	51.4	1993	266,114	56.8%
1994 - 95 71.2 1995 62,1 1996 316,629 1995 - 96 72.8 1996 60.0 1996 333,011 1995 - 96 72.8 1997 66.4 1997 344,483 1996 - 97 80.9 75.4 1999 384,630 1998 - 99 80.9 1999, 75.4 2000 412,170 2000 - 01 95.1 2001 413,690 384,630 2001 - 02 85.0 2002 81.8 2001 413,690 2001 - 02 85.0 2002 81.3 2001 413,690 2002 - 03 85.0 2002 435,248 2001 460,160 2002 - 04 96.5 2003 88.5 2003 463,640 2002 - 05 10.1 2003 88.5 2003 465,428 2003 - 06 10.1 2003 88.5 2003 465,428 2004 - 11.7 2004 88.5 2003 416,401 417,42 2005 -	3	1993 - 94	63.8	1994	8.09	1994	289,280	51.8%
1995 - 56 72.8 1996 65.0 1996 333,011 1997 - 58 75.4 1997 66.4 1997 344,483 1997 - 58 75.4 1998 73.3 1998 384,630 1997 - 58 80.9 1999, 7.6.9 1999 384,630 1998 - 50 83.1 2000 412,170 2000 - 01 85.0 2002 81.8 2001 413,690 2001 - 02 85.0 2002 81.3 2002 456,248 2001 - 02 85.0 2002 81.3 2002 456,248 2002 - 03 96.1 2003 81.3 2002 460,160 2002 - 03 96.1 2003 88.5 2002 460,160 2003 - 04 10.1 2003 88.5 2005 416,742 2004 - 05 10.1 2004 88.5 2005 416,742 2005 - 06 10.1 2004 88.6 2005 517,672 2006 - 07			71.2	1995	62,1	1995	316,629	50.8%
1996 - 97 69.2 1997 66.4 1997 344,483 1997 - 98 75.4 1998 73.3 1998 363,461 1997 - 98 75.4 1999 76.9 184,620 184,620 1999 - 60 88.1 2000 412,170 412,170 2000 - 01 85.1 2001 415,60 446,248 2001 - 03 86.1 2002 446,248 460,160 2001 - 03 86.1 2003 435,574 460,160 2001 - 04 96.5 2004 88.5 2002 446,160 2001 - 05 103.1 2005 88.5 2002 446,160 2004 - 05 107.1 2005 88.5 2007 416,142 2006 - 0 107.1 2005 88.5 2007 416,140 2007 - 0 115.6 2010 106.1 2010 416,240 2008 - 1 115.7 2012 118.4 2011 553,60 2009 - 1 1		1	72.8	9661	0.69	9661	333,011	52.2%
1997, 98 75.4 1998 73.3 1998 36,461 1998, 90 80.9 1999, 7 76.9 1999 38,630 1999, 60 83.1 2000 78.4 2000 412,170 2000, 01 95.1 2001 81.8 2001 412,170 2000, 01 95.1 2002 81.8 2001 412,170 2000, 01 96.1 2002 81.3 2002 412,170 2001, 02 85.0 2002 81.3 2002 412,170 2001, 03 96.5 2002 81.3 2003 440,160 2002, 04 96.5 2003 88.5 2003 446,160 2004, 05 103.1 2003 91.8 2003 446,160 2006, 07 111.7 2007 91.8 2007 445,34 2006, 07 111.7 2003 98.6 2003 445,34 2007, 08 115.6 2009 103.5 2004 460,160 </td <td></td> <td>i i</td> <td>69.2</td> <td>1997</td> <td>69.4</td> <td>1997</td> <td>344,483</td> <td>56.8%</td>		i i	69.2	1997	69.4	1997	344,483	56.8%
1998, 99 80.9 1999, 7 76.9 1999 384,630 1999, 00 4311 2000 78.4 2000 412,170 2000 - 01 95.1 2001 81.8 2001 413,690 2000 - 02 83.0 2002 81.3 2002 436,248 2001 - 02 85.0 2002 81.3 2003 436,248 2002 - 03 96.1 2003 436,248 461,60 2003 - 04 96.5 2004 85.3 2004 461,60 2004 - 05 107.1 2005 91.8 2004 495,930 2005 - 06 107.1 2005 91.8 2004 495,930 2006 - 07 111.7 2007 95.6 2007 517,994 2007 - 08 115.6 2009 103.5 2009 563,692 2008 - 09 121.2 2009 103.5 2009 563,692 2009 - 10 124.6 2013 115.0 2013 610,681 <td></td> <td>1</td> <td>75.4</td> <td>8661</td> <td>73.3</td> <td>1998</td> <td>363,461</td> <td>\$5.0%</td>		1	75.4	8661	73.3	1998	363,461	\$5.0%
1999 - 60 83.1 2000 78.4 2000 412,170 2000 - 01 95.1 2001 81.8 2001 413,690 2000 - 01 85.0 2002 83.8 2002 436,248 2001 - 02 85.0 2003 81.3 2003 435,574 2002 - 03 96.1 2003 81.3 2003 435,574 2002 - 03 96.5 2004 88.5 2003 445,274 2004 - 05 103.1 2005 88.5 2005 445,40 2005 - 06 107.1 2006 91.8 2006 445,40 2006 - 07 111.7 2006 103.5 2006 517,994 2006 - 08 113.6 2009 103.5 2009 517,994 2007 - 08 113.4 2011 108.4 2011 518,96 2008 - 09 113.4 2013 115.0 2013 517,994 2010 - 11 137.4 2013 118.5 2014	12.		80.9	1999,	16.9/	1999	384,630	54.3%
2000 - 01 95.1 2001 81.8 2001 413,690 2001 - 02 85.0 2002 83.8 2002 436,248 2001 - 02 85.0 2003 81.3 2003 435,74 2002 - 03 96.1 2003 81.3 2003 435,74 2002 - 03 96.5 2004 85.3 2004 460,160 2004 - 05 103.1 2005 88.5 2005 476,742 2005 - 06 107.1 2006 91.8 2005 476,742 2007 - 08 115.6 2007 98.6 2007 517,994 2007 - 08 115.6 2009 103.5 2009 563,692 2008 - 09 121.2 2009 103.5 2009 563,692 2008 - 10 124.6 2019 108.4 2011 592,175 2010 - 11 137.7 2012 118.3 2014 651,599 2010 - 11 134.3 2014 118.5 2014	-	1	83.1	2000	78.4	7000	412,170	. %9:95
2001 - 02 85.0 2002 436,248 2002 - 03 96.1 2003 81.3 2003 435,574 2002 - 03 96.1 2003 81.3 2004 460,160 2004 - 05 103.1 2005 88.5 2005 476,742 2004 - 05 103.1 2005 91.8 2006 476,742 2004 - 05 107.1 2005 91.8 2006 476,742 2005 - 06 107.1 2006 91.8 2006 476,742 2006 - 07 111.7 2007 95.6 2007 517,954 2007 - 10 121.2 2009 106.1 2010 578,796 2008 - 10 124,6 2010 106.1 578,796 2010 2010 - 11 127,7 2011 108.4 2011 578,796 2011 - 12 131.4 2012 111.3 2012 610,81 2011 - 12 134.4 2013 115.0 2014 651,594 <tr< td=""><td></td><td>2000 - 01</td><td>95.1</td><td>2001</td><td>81.8</td><td>2001</td><td>413,690</td><td>49.7%</td></tr<>		2000 - 01	95.1	2001	81.8	2001	413,690	49.7%
2002 - 03 96.1 2003 81.3 2003 435,574 2003 - 04 96.5 2004 85.3 2004 460,160 2004 - 05 103.1 2005 88.5 2005 476,742 2005 - 06 107.1 2006 91.8 2006 495,930 2006 - 07 111.7 2007 98.6 2006 495,930 2007 - 08 115.6 2008 98.6 2008 537,112 2008 - 0 121.2 2009 103.5 2009 563,692 2009 - 10 124.6 2010 106.1 578,996 82,175 2009 - 10 124.6 2010 106.1 578,996 82,175 2009 - 10 124.6 2011 108.4 2011 58,796 82,175 2010 - 11 127.7 2011 108.4 2011 578,996 82,175 2011 - 12 131.4 2012 118.5 2014 611,594 2012 - 13 145.2 <td< td=""><td></td><td>2001 - 02</td><td>85.0</td><td>2002</td><td>83.8</td><td>2002</td><td>436,248</td><td>58.6%</td></td<>		2001 - 02	85.0	2002	83.8	2002	436,248	58.6%
2003 - 04 96,5 2004 85.3 2004 460,160 2004 - 05 103.1 2005 88.5 2005 476,742 2005 - 06 107.1 2006 91.8 2006 495,930 2006 - 07 111.7 2007 95.6 2008 495,930 2006 - 07 111.7 2007 95.6 2008 495,930 2007 - 08 115.6 2008 98.6 2008 537,112 2009 - 10 124.6 2010 106.1 2010 578,796 2009 - 10 124.6 2010 106.1 2010 578,796 2009 - 10 124.6 2010 106.1 2010 578,796 2010 - 11 127,7 2011 118.5 2011 592,175 2011 - 12 134.3 2012 118.5 2013 61,801 2012 - 13 146.7 2014 18.5 2014 61,804 2012 - 14 146.7 2015 142.5 2019 </td <td></td> <td>2002 - 03</td> <td>96.1</td> <td>2003</td> <td>81.3</td> <td>2003</td> <td>435,574</td> <td>51.7%</td>		2002 - 03	96.1	2003	81.3	2003	435,574	51.7%
2004 - 05 103.1 2005 88.5 2005 476,742 2005 - 06 107.1 2006 91.8 2006 495,930 2006 - 07 11.7 2007 95.6 2007 517,994 2007 - 08 115.6 2008 98.6 2008 537,112 2008 - 09 121.2 2009 103.5 2009 563,692 2009 - 10 124.6 2010 106.1 2010 578,796 2009 - 10 124.6 2010 106.1 2010 578,796 2009 - 10 124.6 2011 108.4 2011 592,175 2010 - 11 127.7 2011 108.4 2011 592,175 2011 - 12 131.4 2012 1118.5 2014 651,599 2012 - 13 136.3 115.0 2014 651,599 671,994 2012 - 14 140.7 2014 118.5 2014 651,599 2014 - 15 144.1 2015 125.0 <	4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2003 - 04	96.5	2004	85.3	2004	460,160	54.4%
2005 - 06 107.1 2006 91.8 2006 495,930 2006 - 07 111.7 2007 95.6 2007 517,994 2007 - 08 115.6 2008 98.6 2008 537,112 2008 - 09 121.2 2009 103.5 2009 563,692 2009 - 10 124.6 2010 106.1 2010 578,796 2010 - 11 127.7 2011 108.4 2011 592,175 2010 - 11 127.7 2011 108.4 2011 592,175 2011 - 12 131.4 2012 111.3 2012 610,81 2012 - 13 136.3 2013 115.0 2014 651,599 2012 - 14 140.7 2014 118.5 2014 651,599 2014 - 15 145.2 2015 125.0 611,594 2015 2015 - 16 149.1 2015 125.0 2016 651,774 2015 - 17 154.4 2017 142.5		2004 - 05	103.1	2005	88.5	2002	476,742	52.8%
2006 - 07 11.7 2007 95.6 2007 517,994 2007 - 08 115.6 2008 98.6 2008 537,112 2008 - 09 121.2 2009 103.5 2009 563,692 2009 - 10 124.6 2010 106.1 2010 578,796 2010 - 11 127.7 2011 108.4 2011 592,175 2011 - 12 131.4 2012 111.3 2012 610,681 2012 - 13 136.3 2013 118.5 2014 611,681 2013 - 14 140.7 2014 118.5 2014 611,599 2014 - 15 145.1 2014 118.5 2014 611,599 2015 - 16 149.1 2014 118.5 2014 611,599 2016 - 17 154.4 2015 125.0 2016 691,774 2019 - 2020 171.0 2021 142.5 2029 703,982 2019 - 2020 177.0 2021 142.5		2005 - 06	107.1	2006	91.8	7006	495,930	52.9%
115.6 2008 98.6 2008 537,112 121.2 2009 103.5 2009 563,692 124.6 2010 106.1 2010 578,796 127,7 2011 108.4 2011 592,175 131.4 2012 115.0 2013 610,681 136.3 2013 115.0 2013 610,681 140.7 2013 115.0 2013 610,681 140.7 2013 118.5 2014 651,599 145.2 2014 651,599 2014 651,599 145.1 2015 125.0 2015 671,994 154.4 2016 125.0 2016 691,774 159.7 2016 133.5 2016 691,774 155.7 2018 134,536 2019 766,664 165.5 2019 142.5 2020 793,982 170 2021 147.2 2021 819,951 188.4		2006 - 07	111.7	2007	92.6	2007	517,994	52.9%
121.2 2009 103.5 2009 563,692 124.6 2010 106.1 2010 578,796 127,7 2011 108.4 2011 592,175 131.4 2012 115.0 610,681 136.3 2013 115.0 2013 631,207 140.7 2013 118.5 2014 651,599 2014 145.2 2014 651,599 2015 671,994 2015 125.0 2016 691,774 149.1 2016 125.0 2016 691,774 2016 691,774 159.7 2016 133.5 2016 793,50 2017 714,536 159.7 2018 133.5 2018 739,20 2018 739,20 159.7 2020 142.5 2020 793,882 2020 793,882 177.0 2021 147.2 2021 819,951 2022 845,340 188.4 2023 156.1 2024 <td< td=""><td></td><td>2007 - 08</td><td>115.6</td><td>2008</td><td>98.6</td><td>2008</td><td>537,112</td><td>53.0%</td></td<>		2007 - 08	115.6	2008	98.6	2008	537,112	53.0%
124.6 2010 106.1 2010 578,796 127.7 2011 108.4 2011 592,175 131.4 2012 115.0 610,681 610,681 136.3 2013 631,207 631,207 140.7 2014 651,599 610,681 140.7 2014 118.5 2014 651,599 145.2 2015 122.0 2015 671,994 691,774 149.1 2016 125.0 2016 691,774 691,774 159.7 2016 133.5 2018 739,200 691,774 159.7 2018 133,5 2018 739,200 664 155.7 2018 133,5 2019 766,664 664 171.0 2020 142.5 2020 793,882 774 182.6 2022 151.5 2022 845,340 872,497 188.4 2023 156.1 2024 901,280 901,280		2008 - 09	121.2	2009	103.5	2009	563,692	53.1%
127.7 2011 108.4 2011 592,175 131.4 2012 (111.3) 2012 610,681 136.3 2013 115.0 2013 631,207 140.7 2014 118.5 2014 651,599 145.2 2015 122.0 2015 671,994 145.1 2016 125.0 2016 691,774 154.4 2017 129.3 2017 714,536 159.7 2018 133.5 2018 739,200 155.7 2019 138.2 2018 766,664 171.0 2020 142.5 2020 793,982 182.6 2022 151.5 2021 819,551 188.4 2023 156.1 2023 872,497 194.0 2024 160.6 2024 901,280		2009 - 10	124.6	2010	1.901	2010	578,796	53.0%
131.4 2012 610,681 136.3 2013 610,681 136.3 2013 631,207 140.7 2014 651,599 145.2 2015 2014 651,599 145.2 2015 2016 691,774 149,1 2016 125.0 2016 691,774 154,4 2017 129.3 2017 714,536 159,7 2018 133.5 2018 739,200 165.5 2019 138.2 2019 766,664 171.0 2020 142.5 2020 793,982 177.0 2021 147.2 2021 819,951 188.4 2023 156.1 2023 872,497 194.0 2024 5024 901,280		2010 - 11	127.7	2011	108.4	2011	592,175	52.9%
136.3 2013 115.0 2013 631,207 140.7 2014 118.5 2014 651,599 145.2 2015 122.0 2015 671,994 145.1 2016 125.0 2016 691,774 149,1 2017 129,3 2017 714,536 154,4 2017 129,3 2018 739,200 159,7 2018 138,2 2019 766,664 165,5 2019 142,5 2020 793,982 171,0 2021 147,2 2021 819,951 182,6 2022 151,5 2022 845,340 188,4 2023 156,1 2024 901,280 194,0 2024 2024 901,280 1		2011 - 12	131.4	2012	11113	2012	610,681	53.1%
140.7 2014 118.5 2014 651,599 145.2 2015 122.0 2015 671,994 149.1 2016 125.0 2016 691,774 154.4 2017 129.3 2017 714,536 159.7 2018 739,200 739,200 165.5 2019 766,664 739,200 171.0 2020 142.5 2020 793,982 177.0 2021 147.2 2020 793,982 185.6 2022 151.5 2022 845,340 188.4 2023 156.1 2023 872,497 194.0 2024 2024 901,280		2012 - 13	136.3	2013	115.0	2013	631,207	52.9%
145.2 2015 122.0 2015 671,994 149.1 2016 125.0 2016 691,774 154.4 2017 129.3 2017 714,536 159.7 2018 739,200 714,536 165.5 2019 739,200 739,200 165.5 2019 766,664 766,664 171.0 2020 142.5 2020 793,982 177.0 2021 147.2 2021 819,951 182.6 2022 151.5 2022 845,340 188.4 2023 156.1 2023 872,497 194.0 2024 2024 901,280		2013 - 14	140.7	2014	118.5	2014	665,159	52.9%
149.1 2016 125.0 2016 691,774 154.4 2017 129.3 2017 714,536 159.7 2018 739,200 739,200 165.5 2019 766,664 766,664 171.0 2020 142.5 2020 793,982 177.0 2021 147.2 2021 819,951 182.6 2022 151.5 2022 845,340 188.4 2023 156.1 2023 872,497 194.0 2024 160.6 2024 901,280		2014 - 15	145.2	2015	122.0	2015	671,994	52.8%
154.4 2017 129.3 2017 714,536 159.7 2018 133.5 2018 739,200 165.5 2019 138.2 2019 766,664 171.0 2020 142.5 2020 793,982 177.0 2021 147.2 2021 819,951 182.6 2022 151.5 2022 845,340 188.4 2023 156.1 2023 872,497 194.0 2024 160.6 2024 901,280		2015-16	149.1	2016	125.0	2016	691,774	53.0%
159.7 2018 133.5 2018 739,200 165.5 2019 138.2 2019 766,664 171.0 2020 142.5 2020 793,982 177.0 2021 147.2 2021 819,951 182.6 2022 151.5 2022 845,340 188.4 2023 156.1 2023 872,497 194.0 2024 160.6 2024 901,280		2016 - 17	154.4	2017	129.3	2017	714,536	52.8%
165.5 2019 138.2 2019 766,664 171.0 2020 142.5 2020 793,982 177.0 2021 147.2 2021 819,951 182.6 2022 151.5 2022 845,340 188.4 2023 156.1 2023 872,497 194.0 2024 2024 901,280		2017 - 18	159.7	2018	133.5	2018	739,200	52.8%
171.0 2020 142.5 2020 793,982 177.0 2021 147.2 2021 819,951 182.6 2022 151.5 2022 845,340 188.4 2023 156.1 2023 872,497 194.0 2024 2024 901,280		2018 - 19	165.5	2019	138.2	2019	766,664	52.9%
177.0 2021 147.2 2021 819,951 182.6 2022 151.5 2022 845,340 188.4 2023 156.1 2023 872,497 194.0 2024 301,280		2019-2020	171.0	2020	142.5	2020	793,982	53.0%
182.6 2022 151.5 2022 845,340 188.4 2023 156.1 2023 872,497 194.0 2024 \$160.6 2024 901,280		2020-2021	177.0	2021	147.2	2021	819,951	52.9%
188.4 2023 156.1 2023 872,497 194.0 2024 \$160.6 2024 901,280	-	2021-2022	182.6	2022	151.5	2022	845,340	52.9%
194.0 2024 3 160.6 2024 901,280	نو _ر نو _ر	2022-2023	188.4	2023	, 156.1	2023	872,497	52.9%
	The state of the s	2023-2024	194.0	2024	9.091	2024	901,280	53.0%

-

Long Range Planning Study

A Long Range engineering analysis has been performed for the entire SEC system and two Long Range Plans (LRP)'s have been developed. The Plans are named "A" and "B." The preferred plan will be called Plan A and the alternative plan will called Plan B.

Both plans were designed to meet the projected requirements that are consistent with the System Planning Criteria outlined on page V-1. The plans are divided into five load levels or "blocks."

The "A" block spans 1999-2000 and corresponds exactly with the final two years of the present SEC 4-year Construction Work Plan. The "B" block spans 2002-2004. The "C" block spans 2005-2009. The "D" block spans 2010-2014. The last block, "E" spans 2015-2019. These blocks should be considered as loading levels and not exact time frames. The farther into the future of a system that one looks, the less certain the actual time frame. However, load levels are not time-dependent.

The exact time of each improvement will be dictated by actual load growth. The LRP is reviewed before each construction work plan and generally must be followed - although with considerable flexibility at times.

Existing system facilities have been utilized as much as possible in both plans. The 2019 system will have adequate capacity and will provide excellent reliability to more than 20,000 members over 2,200 miles of line at 2.4 times the existing system peak load level.

The projections used to grow the existing system out to the 2019 load level are consistent with the 1996 Power Requirements Study (PRS). This study is performed every two years in conjunction with EKP. The study is based on detailed distribution system information as well as regional demographic and energy usage data.

Growth Method

The future system was "grown" based on the EKP Power Requirements Study. However, in order to apply detailed growth patterns to the system, further investigation was needed. The comprehensive plans for Henry and Shelby counties were consulted. The land-use portion of these reports were extensively reviewed. Water districts in Carroll, Trimble and Henry counties were visited and future expansion plans were noted.

The State of Kentucky highway planning group KIPDA was consulted about the current transportation plans in the SEC service area. Areas of future highway construction or expansion were grown accordingly.

A SEC system map was then color coded based on relative levels of projected system growth for the twenty year period. With this map and the PRS data, specific areas of the system could be "grown" at different rates on the distribution system analysis software (Windmill by Milsoft). The result is system computer models with very site specific load growth levels.

Growth Areas

Over the past ten years, the vast majority of system growth has been Shelby County. The Shelby Industrial Park and its nearby surroundings contain an area where Industrial & Commercial growth has been consistent and substantial. This area is intersected by Interstate 64 and is 30 miles from downtown Louisville, Kentucky. The Budd Plant, Bekaert, Omega Plastics and Lawson Mardon are the four largest industrial loads on the system. All four are served by substations located in and around the Industrial Park area. Further expansion is projected in this area due to available land that is favorably located.

Norfolk Southern railroad operates a vehicle shipping terminal in this area. With a large amount of available land at this site, it is anticipated that a major automotive producer will locate an assembly plant at or in this vicinity.

The northwestern tip of Shelby County is another area that has and will continue to see substantial growth in the residential category. The Long Run area is a dynamic residential growth area near the Jefferson County line. This location, with its easy access to Louisville, will continue to expand in the years to come. The proposed Long Run Substation is discussed in this report. The planned construction of Long Run in 2000 will improve voltage, greatly reduce line exposure and provide a higher quality of service to a vast area in western Shelby County.

The Pendleton area of western Henry County is another pocket of substantial future growth. Interstate 71 exits at this site have already made it a significant commercial area. With Cincinnati, Ohio one hour to the north and Louisville, Kentucky one-half hour to the south, commercial and residential growth is projected to continue at a steady rate.

A small area in and around Milton Substation has been projected to grow at a significant level. A good highway and water and sewer in this immediate area will promote residential growth.

Several other small pockets of strong future growth exist throughout the system. However, in general, all of Carroll County and the eastern half of Henry County were projected to have light growth due to the proposed land uses which are affected by soil, topography and reduced highway and water systems. Much of rural Shelby County is also restricted to low density development which was outlined in its comprehensive plan.

				1-		SIGNATIO			DATE PLANA		RT COMPLE	TED	\Box
S		OF SYST				SHE			JULY	T338			- 1
	PLANNIN	IG REPOR	iT.	1				ם ר					
							DGES,	LLE	L				\dashv
······································						ENERAL	DATA						_
L	Z. LINE	MILES	3. NO. OF	CONSUMERS	1		TOTAL	77	DTAL	7. PA	ST PEAK LO	DESIGN	
ITEMS	TRANS.	DISTR.	ALL TYPES		SYS'	TEM :	SPECIAL DADS (HW)	YEAR	LY SALES	kWtvCO		LOAD KWIVCON TE MOS.	NS.
1.	a.	ь.	special load	r) d.	4		5.		6.		ь	PEAK MO	ο.
					<u> </u>								\neg
PRESENT SYSTEM AS OF													
12/31/97	00	1,786	11,290	10	69,8	31 26	500	328,39	16,178	-2.85	8 1-9	7 2,858	8
LONG RANGE	_												
PLAN	0	2,220	20,000) 15	174,	000 4	0,000	665,00	0,000			3,266	5
		•			PARTII	LINE	AILES						
ITEMS	,			2 DISTRIBUT	NON					3. TRANSA	AISSION		
		12.5 / 7.2 K	V 24.9	114.4 KV	k'	,	kV		kV	kV	×	vx	kν
1.		Ł		b	c. ^		d	. 1	- ```	ъ.	^	d. `	``
PRESENT SYSTEM	AS			· ·									
OF		1,691	95	5	0		0	0		0	0	0	
101000												•	
LONG RANGE PLAN	4	1,989	23	1	0	-	0	0		0	0	0	
	***************************************		PAR	TIII SUBS	MOITATE	IS AND	METERIN	NG POIN	rs		·····		
1. PRESENT SYSTEM A. LONG RANGE PLAN													
NAME OF LOC	ATION	POWER SI	וחמו ודם		T	kV		ίV			kV	kV	
NAME OF LOC.	ATION	POWER SC		MVA	F	D.		NDARY	MVA *-	P	RIMARY b.	SECONDAR'	ťΥ
Logan I		E)		18.		69	2		18.1		69	25	
Clay Villa	200	El El		15.		69	12		18.1		69	12.5	
NewCastle	186	E		15.		69	12		15.7		69	12.5	
Campbells		E		15.		69	12		18.1		69	12.5	
Bedford	burg .		CP	15.		69	12		18.1		69	12.5	
			KP	7.		69		.5	15.7		69	12.5	
Southville	2					69	12		15.7		69	12.5	
Milton			KP.	4.		69	13		18.1		69	13.2	
Budd			KP .	18.		69		5	30.0		69	25	 -
Bekaert I		1	KP	15.		69	2		30.0		69	25	
Logan II		ļ	KP										
Jericho			KP.	15.		69		5	18.1		69	12.5	
Bekaert I			KP	15.		69		5	30.0		69	25	
Bluegrass	Tie	Bluegr		1.	8	25	12	5	1.8		25	12.5	
Long Run			KP						5.6		69	2.5	
Todds Poi			KP	<u> </u>	=====				15.7		69	25	
Clay Vill			KP						15.7		69	25	
Bedford I	I	E	KP						15.7		69	25	
		<u> </u>											
			PART	IV INVES	IMENT	IN PLAN	IT (Thous	ands of D					
ITEMS		TRANSMIS LINE 2.		ALL SUBSTATION 3.			ISFORMERS SERVICES		HER DISTR. CILITIES 5.	PL	LTLD ANT 6.	GENERAL & PROD. PLAN 7.	
PRESENT SYSTEM	A AS	0		0	\$1	0,388		\$23,8	856,863				
<u> </u>		+		÷ 0		5,633				\$74,20			

SHELBY CWP: I-A Page 1

PURPOSE OF REPORT

This report documents the engineering analysis of, and summarizes the proposed construction for Shelby Energy Cooperative, Inc.'s (SEC) electric distribution system for the four-year planning period of 2001-2004

The report also provides engineering support in the form of descriptions, costs and justifications of the required new facilities for a loan application to RUS in order to finance the proposed construction program.

GENERAL BASIS OF STUDY

The winter 2003 and winter 2005 projected total peak system loads were taken from the SEC 2000 Power Requirements Study (PRS) as approved by RUS. Residential and small commercial loads were grown at rates consistent with the PRS.

From 1994-1999, the annual increase in residential energy sales was 5.9%. This rate is projected to be 4.1% over the next four years. Small commercial sales are projected to increase at 2.9% over the next four years. There is a 5.7% projected increase in large commercial energy sales over the next four years.

System analysis models are based on ten-year, non-coincidental (NC) system peaks that are outlined in the PRS. The projected winter 2005 NC peak (based on PRS and GFR meeting) is 112,000 kW. The system annual load factor is projected to average 54.6% over the next four years.

Existing winter and summer growth models were examined for what is a winter-peaking system. The existing summer model was reviewed to ensure that any system deficiencies for the cooling load closely tracked the winter model. This was determined to be the case.

The SEC 1999-2018 Long Range Plan (LRP) load projections and improvement recommendations were reviewed and they generally agree with scope of the 2001-2004 CWP recommendations. A review of the LRP is included in this report.

A RUS Operations and Maintenance Survey (FORM 300) has been completed with the RUS GFR. This survey is used to determine portions of the construction required to replace physically deteriorated equipment and material, upgrade areas of the system to conform to code or safety requirements, and improve the reliability and quality of service. A copy of the survey is included in the Appendices of this report.

SHELBY CWP: I-A Page 2

GENERAL BASIS OF STUDY (cont.)

A system analysis using RUS guidelines and the SEC Design Criteria was performed on all of the substations and distribution lines of the system Milsoft Integrated Solutions' PC-Based Distribution Analysis Program – "Windmil" was used to analyze the existing system configuration that was modeled with the projected load growth.

For each deficiency that was found, alternate solutions were considered and economically evaluated.

SUMMARY - RESULTS OF PROPOSED CONSTRUCTION

Upon completion of the proposed construction, the system will provide adequate and dependable service to 13,770 residential customers as well as 12 large power loads and 381 small commercial loads. Average monthly residential usage is projected to be 1,263 kWh. It is estimated that there will be 1,300 idle services.

There are no new substations or existing station upgrades proposed during the construction work plan period.

A majority of this plan deals with the replacement of single-phase conductor. There are several three-phase conductor replacements. 133 circuit miles of conductor replacement and conversion will take place in the four-year plan period. Conductor replacement line sections were selected based on conductor condition, operational experience and the number of customers served.

Feeders out of Campbellsburg, Logan II, Clayvillage and Southville will be rebuilt or rehabilitated in order to further strengthen the backbone of the system.

The largest system improvement is a three-phase express feed from the Jericho substation into the growing Pendleton/I-71 area.

SHELBY CWP: I-C

Page 1

SUMMARY OF CONSTRUCTION PROGRAM AND COSTS

Shelby Energy Cooperative's distribution system was analyzed in order to identify the construction requirements needed to adequately serve the projected CWP load of 112 MW. Improvements were identified based on voltage drop, conductor loading, system reliability improvement, economic conductor analysis and operational experience. A narrative list of system improvements is located in Section IV.

A breakdown of proposed construction projects by RUS 740C codes is listed below in Table I-C-1.

Table I-C-1
System Additions and Improvements Summary

RUS Form 740C Category	Category Name	Estimated Cost
100	New Distribution Line	\$4,600,000
300	Line Conversion &	\$3,584,130
	Replacement	
600	Misc. Equip & Poles	\$3,263,735
700	Security Lights/SCADA	\$278,270
	2001-2004 CWP TOTAL	\$11,726,135

100 - New Construction planned to serve 2,300 new services.

300 – 152 miles of conductor upgrading, replacement and feeder rehabilitation.

600 – Miscellaneous distribution equipment and pole changes. This includes voltage regulators, capacitors, sectionalizing, meters, transformers, auto-transformers, pole changes and increased service capacity upgrades.

700 - Other Distribution Items - Security Lights 702 & SCADA 703.

APPENDIX B

APPENDIX TO AN ORDER OF THE KENTUCKY PUBLIC SERVICE COMMISSION IN ADMINISTRATIVE CASE NO. 2005-00090 DATED MARCH 10, 2005

2. Are new technologies for improving reliability, efficiency and safety investigated and considered for implementation in your power generation, transmission and distribution system?

Safety, reliability and efficiency are hallmarks of Shelby Energy's commitment to its member/owners. Toward fulfilling this commitment the Cooperative is continually reviewing industry applicable technologies that will enhance these vital elements of service. In our most recent four year construction work plan (CWP 2001-2004) the cooperative committed to begin installation of system control and data acquisition (SCADA) on each of its distribution feeder circuits. To date, approximately eighty percent (80%) of Shelby's distribution system SCADA is complete. Plans are to have entire SCADA coverage of the distribution system by 2006. Presently, Shelby is partnering with neighboring cooperative Owen Electric to provide 24 hour seven days a week monitoring of the SCADA system.

Additionally, Shelby along with ENVISION Energy Services has installed I-grid technology, power quality monitors in substations that serve particularly sensitive commercial and industrial loads. With this technology, the cooperative is able to respond promptly to system events that cause power quality issues.

In 2003, Shelby embarked on a project to convert its paper based mapping system to a fully digital based system. This project is scheduled for completion in 2005. It will feature open architecture with "multi-speak" capability that will enable this seamless, sub-meter accurate map of the distribution system to become a platform for distribution system modeling, plant record maintenance and outage and work management systems.

Shelby is also employing remote metering reading technology to collect monthly meter readings at remote and/or difficult to access consumer sites. While the cooperative is continuing to utilize contracted meter reading services, it is also evaluating not only the remote read ERT technology, but also the implementation of system-wide automated metering reading (AMR) technology.

East Kentucky Power Cooperative is responding on behalf of Shelby Energy Cooperative concerning the generation and transmission.

5. Provide actual and weather-normalized annual coincident peak demands for calendar years 2000 through 2004 disaggregated into (a) native load demand, firm and non-firm; and (b) off-system demand, firm and non-firm.

The numbers below represent firm, native load.

			Min. Peak	Seasonal	
	Actual coincident	Temp		Profile Temp	
	peak demand (MW)	Coef	(Degrees F)	(Degrees F)	coincident peak demand (MW)
Dec. 2000	81	-0.64	10	2	86
Jan. 2001	82	-0.74	6	2	85
Mar. 2002	79	-0.73	11	2	85
Jan. 2003	89	-0.74	6	2	92
Jan. 2004	89	-0.72	-1	2	87

Based on Louisville Weather Station Data and Shelby Energy Hourly Load Data




- 17. Provide a summary description of your utility's existing demand-side management ("DSM") programs, which includes:
 - a. Annual DSM budget,
 - b. Demand and energy impacts,
 - c. The currently scheduled termination dates for the programs.

Shelby Energy and East Kentucky Power Cooperative work together to design DSM programs. Program implementation is done by Shelby Energy, with support by EKPC. DSM programs are exclusively residential in nature, and almost always involve HVAC or water heating efficiency measures.

DSM programs currently in place are as follows:

- 1. Air-Source Heat Pump Incentive
- 2. Button Up Weatherization
- 3. Electric Water Heater Incentive
- 4. Geothermal Heating and Cooling

In 2004, Shelby Energy had the following number of participants.



The next page summarizes the programs.

Button Up Weatherization Program

The program requires the installation of insulation materials or the use of other weatherization techniques to reduce heat loss in the home. Any retail member living in a stick-built or manufactured home that is at least two years old and which uses electric as the primary source of heat is eligible.

Air-Source Heat Pump Incentive

This program promotes efficient air-source heat pumps. The primary targets for this program are retail members building new homes in areas where natural gas heat is an option. An important secondary target is the HVAC retrofit market, offering incentives to retail members to replace electric furnaces and gas or propane heat with high-efficiency electric heat pumps.

Electric Water Heater Incentive

The electric water heater incentive is designed to encourage residential customers engaged in new construction to choose a high-efficiency electric water heater over other available options. It is also designed to encourage conversion from a fossil-fuel water heater to a high-efficiency electric water heater.

Geothermal Heating and Cooling

Traditional air-source heat pumps remove heat from the air. Geothermal heating is a heat pump that removes heat from the ground. It is a very efficient heating and cooling appliance. EKPC and its member systems pioneered the development and implementation of geothermal heating and cooling during the eighties and nineties.

Demand / Energy Impacts And Annual Budget

The table below reports program impacts. Note that this data is per installation.

	Energy Impact (kWh)	Impact On Winter Peak (kW)	Impact On Summer Peak (kW)
Button Up	(2,700)	(2.7)	(1.0)
Geothermal	(6,000)	(3.5)	(1.5)
Efficient Heat Pump In New Construction	(925)	2.5**	(1.0)
Efficient Water Heater	700**	0.2**	0.1**

^{**} Impacts are positive due to customers who normally would have chosen natural gas

Annual budgets are a function of administrative cost and incentive payments. The table below reports EKPC administrative costs, and typical administrative costs and incentive payments by EKPC member distribution cooperatives.

	EKPC Administrative Costs	Distribution Cooperative Administrative Costs*	Incentive Payment
Button Up	\$32	\$163	Up to \$600
Geothermal Energy Home	\$17	\$254	\$900
Efficient Heat Pump In New Construction	\$13	\$182	\$300
Efficient Water Heater	\$8	\$61	\$200

^{*}These costs are averages of all participating member distribution cooperatives, and vary by distribution cooperative.

For a more in depth discussion of EKPC and member distribution cooperative DSM programs, please see Administrative Case No. 2003-00051, Appendix II.

		·	

18. Provide your utility's definition of "transmission" and "distribution".

Transmission is power lines operating at voltages in excess of 25KV.

Distribution is power lines operating at voltages of 25KV or less.

Distribution for Shelby Energy is defined as those facilities we own beyond the low-side of EKPC's distribution substation.

19. Identify all utilities with which your utility is interconnected and the transmission capacity at all points of interconnection.

Shelby Energy has a distribution tie with Bluegrass Energy system. Since each utility is served by EKPC there is no interconnection with other utilities.

East Kentucky Power Cooperative is responding on behalf of Shelby Energy Cooperative concerning the transmission.

20. Provide the peak hourly MW transfers into and out of each interconnection for each month of the last 5 years. Provide the date and time of each peak.

21. Identify any areas on your utility's system where capacity constraints, bottlenecks or other transmission problems have been experienced from January 1, 2003 until the present date. Identify all incidents of transmission problems by date and hour, with a brief narrative description of the nature of the problem. Provide the MW transfers for each of your utility's interconnections for these times.

,		

22. Provide details of any planned transmission capacity additions for the 2005 through 2025 period. If the transmission capacity additions are for existing or expected constraints, bottlenecks, or other transmission problems, identify the problem the addition is intended to address.

23. Is your utility researching or considering methods of increasing transmission capacity of existing transmission routes? If yes, discuss those methods.

24. Provide copies of any reports prepared by your utility or for your utility that analyze the capabilities of the transmission system to meet present and future needs for import and export of capacity.

East Kentucky Power Cooperative is responding on behalf of Shelby Energy Cooperative.



- 25. Provide the following transmission energy data forecast for the years 2005 through 2025.
 - a. Total energy received from all interconnections and generation sources connected to your transmission system.
 - b. Total energy delivered to all interconnections on your transmission system.
 - c. Peak demand for summer and winter seasons on your transmission.

East Kentucky Power Cooperative is responding on behalf of Shelby Energy Cooperative.

		٠	

26. Provide the yearly System Average Interruption Duration Index ("SAIDI") and the System Average Interruption Frequency Index ("SAIFI"), excluding major outages, by feeder for each distribution substation on your system for the last 5 years.

Refer to attachments 26.1 and 26.2

26.1

2000-2004 Entire System MAJOR STORMS NOT INCLUDED

YEAR	SAIDI	SAIFI
2000	3.68	1.69
2001	2.32	1.27
2002	1.61	0.85
2003	1.30	0.76
2004	1.10	0.80

Outages by feeder for each distribution substation are not available for years 2000-2003. Refer to 26.2 for outage by feeder for each distribution substation for year 2004.

26.2

2004 MAJOR STORMS NOT INCLUDED

SUB	FEEDER	SAIDI	SAIFI
1	2	2.15	1.42
1	3	4.22	2.59
1	4	0.10	0.14
	1	0.37	0.38
2 2	2	2.90	1.32
2	3	0.77	1.74
2	4	1.20	0.66
2	5	0.18	0.11
3	1	0.31	0.28
3	2	1.81	1.55
3	3	0.56	0.58
4	1	1.47	0.61
4	2	1.52	0.61
4	3	0.39	0.28
4	4	0.58	0.40
5	1	1.30	0.88
5	2	0.90	0.54
5	3	0.54	0.48
5	4	1.51	0.83
6	1	1.15	1.33
6	2	1.15	0.62
6	3	0.55	0.23
7	1	1.45	0.61
7	2	0.53	0.32
7	3	1.17	0.63
 7	4	5.48	2.11
<u></u>	+ 1	1.84	2.00
8	1 1	0.00	0.00
9	2	0.75	1.00
9	1 1	0.15	0.16
10	+	1.09	0.57
11	1	0.54	0.42
11	3	0.42	0.37
11	1 1	0.00	0.00
12		0.00	0.00
12	2	0.00	0.00
12	3	0.00	0.00
13	1	2.45	2.95
13	2		2.38
BG FEED	11	3.46	2.30

27. Provide the yearly SAIDI and SAIFI, including major outages, by feeder for each distribution substation on your system for the last 5 years. Explain how you define major outages.

Refer to attachments 27.1 and 27.2.

Major outages are outages with consumer hours greater than 10,000 or declared by FEMA.

27.1

2000-2004 Entire System MAJOR STORMS INCLUDED

YEAR	SAIDI	SAIFI
2000	3.68	1.69
2001	3.28	1.42
2002	1.61	0.85
2003	3.57	1.09
2004	3.99	1.16

Outages by feeder for each distribution substation are not available for years 2000-2003. Refer to 27.2 for outages by feeder for each distribution substation for year 2004.

27.2

2004 MAJOR STORMS INCLUDED

SUB	FEEDER	SAIDI	SAIFI
·1	2	5.58	1.92
1	3	4.70	2.67
1	4	1.24	0.50
2	1	0.58	0.43
2	2	6.21	1.73
2	3	11.05	3.45
2	4	10.37	1.41
2	5	44.58	6.11
3	1	1.74	0.41
3	2	5.17	1.79
3	3	2.05	0.79
4	1	3.13	0.78
4	2	2.33	0.73
4	3	5.24	1.67
4	4	1.61	0.55
5	1	1.60	0.91
5	2	2.00	0.68
5	3	2.74	0.70
5	4	4.23	1.18
6	1	4.09	1.49
6	2	13.19	1.66
6	3	10.25	0.88
7	1	1.45	0.61
7	2	0.53	0.32
7	3	1.66	0.69
7	4	5.54	2.11
8	1	1.84	2.00
9	1	0.00	0.00
9	2	0.75	1.00
10	1	0.44	0.25
11	1	2.35	0.74
11	2	7.63	1.56
11	3	2.05	0.63
12	1	0.00	0.00
12	2	0.00	0.00
12	3	0.00	0.00
13	1 1	0.00	0.00
13	2	3.19	3.01
BG FEEL		37.08	4.45

28. What is an acceptable value for SAIDI and SAIFI? Explain how it was derived.

Refer to attachments 28.1 - 28.3.

Shelby Energy Cooperative Inc. has not formally defined acceptable values for SAIDI and SAIFI.

The attached EPRI and Cooper Power Systems information has been reviewed in the past.

Reclosers



Reference Data

Analysis of Distribution System Reliability and Outage Rates

R280-90-7

RELIABILITY ANALYSIS

Reference Data R280-90-7 provides information on methods to measure and improve distribution system reliability and outage rates. Standard indices are described that are used to measure distribution system reliability and calculate improvements. Outage rates goals are discussed and examples of various types of distribution systems are provided, showing logical switchgear applications that will reduce outage rates and improve overall system operation.

Transient and permanent faults are defined and discussed. Transient fault protection schemes including reclosers and fuses for sectionalizing feeder lines and taps are discussed. The difference in fault protection philosophy for overhead versus underground systems is examined. Additional reliability improvements are discussed that can be obtained through system automation by remote identification of faulted sections, coupled with remote switching to isolate the fault and restore service to the rest of the line.

PERFORMANCE INDICES

For discussion of outage rates, performance indices are frequencly used as described in the EPRI report EL-2081. Volume 2, Project 1356-1, pages 3-3 and 3-4. Use of these "standard" indices will permit meaningful comparison between utilities or between different divisions of a given utility, and perhaps most importantly; allow evaluation of system changes by a direct comparison of past and future performance of a feeder or system as changes are made. These standard indices are defined as follows:

System Average Interruption Frequency Index (SAIFI)

Defines the average number of times that a customer's service is interrupted during a year. A customer interruption is defined as one interruption to one customer.

SAIFI = $\frac{\text{total number of customer interruptions}}{\text{total number of customers served}}$

System Average Interruption Duration Index (SAIDI)

Defines the average interruption duration per customer served per year.

SAIDI = sum of customer interruption durations total number of customers

Customer Average Interruption Frequency Index (CAIFI)

Defines the average number of interruptions per customer interrupted per year.

CAIFI = total number of customer interruptions total number of customers affected

Customer Average Interruption Duration Index (CAIDI)

Defines the average interruption duration for those customers interrupted during a year.

 $\text{CAIDI} = \frac{\text{sum of customer interruption durations}}{\text{total number of customer interruptions}} \ .$

Average Service Availability Index (ASAI)

Defines the ratio of the total number of customer hours that service was available during year, to the total customer hours demanded. (customer hours demanded = 24 hours/day x 365 days = 8760 hours)

$$ASAI = \frac{8760 - SAIDI}{8760}$$

For example, a SAIDI of 1.0 hours per year.

$$ASAI = \frac{8760 - 1.0}{8760} = 99.989\%$$

OUTAGE RATE GOALS

For the purposes of this discussion an outage is defined as any loss of service for more than a normal reclosing interval. Many utilities define an outage as loss of service for more than two minutes.

Urban and Rural Systems

Outage rate goals will vary depending upon the nature of the distribution system. Urban systems typically have less line exposure than rural systems. As a result, urban systems experience fewer outages per year than rural systems.

Typical outage rate goals for urban and rural distribution systems are to limit outages to an average of 1.0 (urban) and 1.5 (rural) outages per year (SAIFI). With each outage lasting an average duration of 1 hour (CAIDI), the average annual interruption is 1.0 hours for urban systems and 1.5 hours for rural distribution systems.

Table 1
Typical Utility Outage Rate Goals

Index	System Type	Operating Goal
SAIFI SAIFI CAIDI	Urban Rural Rural/Urban	1.0 Outages Per Year 1.5 Outages Per Year 1.0 Hours Per Outage
SAIDI SAIDI ASAI	Urban Rural Urban	1.0 Outage Hours Per Year 1.5 Outage Hours Per Year 99.989% Annual Service Availability
ASAI	Rural	99,983% Annual Service Availability

Many utilities have found that their service reliability deteriorated significantly when they converted to a higher distribution voltage (for example; 4kV to 13kV). The higher distribution voltage allowed them to service longer feeder lengths and more customers with a given feeder. However, each outage that occurred affected more customers and the longer feeders required more patrol time to locate the fault.

To restore service reliability, the first step is to sectionalize each feeder into smaller sections, limiting the number of customers affected by a given outage and reducing the patrol time needed to locate and repair the fault. Operating experience of a number of utilities that have adopted this sectionalizing practice has suggested that an optimum feeder segment is 3 to 5 MVA. As the load of a line segment approaches 8 to 10 MVA, outage rates increase to unsatisfactory levels.

28.3

reliability indices from a number of sources, including the Internet, utilities, and public service commissions. Next, they analyzed the data in order to evaluate long-term trends, year-to-year variability, and the impact of major events on SAIFI and SAIDI values.

Data from 24 states and 65 utilities, spanning from 1992 to 2001, was analyzed to track the trend of distribution reliability in the United States. Key findings from this analysis follow:

- The 10-year average of SAIDI for all the utilities that exclude major events in their reporting is 107 minutes. This signifies that on average, a customer is expected to experience 107 minutes of sustained interruptions in a given year. Inclusion of major events increases the SAIDI indices on average by 100 percent to a maximum of 1200 percent.
- The 10-year average of SAIFI for all the utilities that exclude major events in their reporting is 1.1. This signifies that on average, a customer is expected to experience 1.1 sustained interruption events in a year. Inclusion of major events increases the SAIFI indices on average by 23 percent to a maximum of 109 percent.

A trend analysis was conducted using data from 1997 to 2001. In this analysis, the 75th percentile showed a decreasing year-to-year trend of SAIFI from 1998 to 2001, but an increasing year-to-year trend of SAIDI from 1997 to 2000 that was reversed in 2001. No noticeable upward or downward trend appeared for the 50th percentile of either SAIFI or SAIDI.

Year-to-year variability of a utility's reliability indices was quantified using the normalized standard deviation index, which is the ratio of standard deviation to mean. In this analysis, the median value of normalized standard deviation for SAIDI is 20.8 percent. Inclusion of major events in the reporting increased this variability to 65.4 percent. Moreover, the median value of normalized standard deviation for SAIFI is 16.6 percent. Inclusion of major events in the reporting increased this variability to 22.3 percent.

EPRI Perspective

Distribution reliability indices are universally used as a performance measure for distribution service quality. EPRI's distribution reliability tracking project is helping to explain the trend and evaluate the variability of these performance indicators, while examining the impact of major events on such indicators. EPRI is leading the effort through its Security, Quality, Reliability, and Availability (SQRA) Program to establish future performance indicators that more closely resemble customer perception of service quality.

Program

2004 Program SST501 Strategic Science & Technology 2004 Program 003.0 Power Quality Solutions for Transmission and Distribution

History

2003 Program 003.0 Power Quality Solutions for Transmission and

29. Provide the yearly Customer Average Interruption Duration Index ("CAIDI") and the Customer Average Interruption Frequency Index ("CAIFI"), including and excluding major outages, on your system for the last five years. What is an acceptable value for CAIDI and CAIFI? Explain how it was derived.

Refer to attachment 29.

	YEAR	CAIDI (Inc. Storm)	CAIFI (Inc. Storm)	CAIDI (No Storm)	CAIFI (No Storm)
,	TEAN		CAIFI (IIIC. Storin)	自己的自己的自己的自己的自己的自己的自己的自己的自己的自己的自己的自己的自己的自	N/A*
١	通常,企业资产的	2.45	11(A*	2.18 hours	
1	2000	2.31 hours	B1/AX	1.83 hours	
	2001		ALLA *	1.88 hours	
	2002		N/A*		N/A*
	2003		BIJA*		ALLA *
	2004	3.45 hours	N/A		

^{*- &}quot;Total Number of Customers Affected is Not Computed by Shelby Energy Cooperative Inc.

The Cooper Power Systems Reference R280-90-7 indicates that 1.0 Hours per Outage is a typical goal for CAIDI.

÷			

30. Identify and describe all reportable distribution outages from January 1, 2003 until present date. Categorize the causes and provide the frequency of occurrence of each cause category.

See attached letter of notification sent to the Public Service Commission on July 14, 2004 for a major wind storm that occurred July 13 and 14, 2004.



To:

Gary Grubbs

PSC

From:

David Graham

System Technical Engineer

Date:

July 14, 2004

Total 591 members without power. 274 members without power for over 4 hours.

- 31. Does your utility have a distribution and/or transmission reliability improvement program?
 - a. How does your utility measure reliability?
 - b. How is the program monitored?
 - c. What are the results of the system?
 - d. How are proposed improvements for reliability approved and implemented?

While Shelby Energy does not have a distribution reliability program in "title", never the less the cooperative has many initiatives that are targeted at tracking and improving the reliability of its distribution system. Again, these initiatives are summarized and coordinated through the cooperative's system planning efforts, namely the long range plan and construction work plan documents.

Reliability is tracked and measured through careful analysis of system outage reports, feedback from operations and engineering personnel as well as the use of "event recorders" at each of the cooperative's critical substations. Consumer feedback is useful in this area as well. Shelby Energy has an active key accounts program where communication with commercial and industrial consumers is valued and is considered vital not only to the success of the cooperative, but also and even more importantly to the success of the consumer.

Repeated events (oil circuit recloser operations, blown fuses, etc.) are investigated and targeted for corrective action. Corrective action can vary depending upon the situation, but can range from "hot spot" tree trimming, protective device maintenance, replacement and/or repair to full scale conductor replacement. Again, each event is evaluated as a function of the cooperative's engineering planning process with replacement projects scheduled such that a balance is struck as much as possible between degree of reliability enhancement for the dollars spent.

- 32. Provide a summary description of your utility's:
 - a. Right-of-way management program. Provide the budget for the last 5 years.
 - b. Vegetation management program. Provide the budget for the last 5 years.
 - c. Transmission and distribution inspection program. Provide the budget for the last 5 years.
 - a. Right-of-way management program.

2000	\$437,343.43
2001	\$385,844.81
2002	\$412,749.00
2003	\$430,792.29
2004	\$523,218:29

b. Vegetation management program.

2000	\$42,134.00
2001	\$29,510.00
2002	\$36,414.00
2003	\$25,276.61
2004	\$3,283.20

c. Distribution inspection program. (Ground Patrolling and Pole Treating)

2000	\$29,891.88
2001	\$24,767.00
2002	\$22,844.00
2003	\$68,709.48
2004	\$29,496.53

East Kentucky Power Cooperative will be responding to the transmission inspection program on behalf of Shelby Energy Cooperative.

Explain the criteria your utility uses to determine if pole or conductor replacement is necessary. Provide costs/budgets for transmission and distribution facilities replacement for the years 2000 through 2025.

A number of factors enter into the criteria that Shelby uses in determining when replacement and improvement of existing distribution plant facilities are necessary. Input is received from operations personnel, annual ground and aerial patrol reports, analyses of outage records and annual operations and maintenance reviews with RUS field representative(s). All of this information on system performance is distilled into a design criteria that becomes the basis for project evaluation and planning in the Cooperative's 20 year, long range plan, and subsequent four year construction work plans and annual work plans and budgets. An example of this criteria found in the Cooperative's 1997-2000 four year construction work plan included the following:

"Conductors and associated poles and hardware will be considered for replacement if any of the following conditions exist:

- a. More than 3 outages or 10 outage-hours per year (excluding major storm and power supplier) for two out of the past three years.
- b. Conductors with an average of greater than one splice per phase conductor per span in one mile increments.
- c. Ordinary replacement of old, deteriorated conductor on a systematic basis.
- d. A significant amount of load that is served by aged, faulty conductor will be considered for re-feeding if a more efficient route on existing right-of-way can be found.
- e. Poles and/or crossarms to be replaced if found to be physically deteriorated by visual inspection and/or other testing methods."

(SEE ATTACHED SUPPORTING DOCUMENTS - EXHIBIT "A")

East Kentucky Power Cooperative is responding on behalf of Shelby Energy Cooperative concerning the transmission.

Shelby CWP: II-A1

Page 1

SPECIFIC SYSTEM CRITERIA SHELBY RECC CONSTRUCTION WORK PLAN 1997 - 2000

- 1. The minimum primary voltage on the system referred to the 120 volt secondary is 118 volts. Downline voltage regulation will be limited to one set of regulators for any given circuit.
- 2. Primary conductors will not be loaded over 75% of their thermal rating.
- The following equipment will have a minimum loading not to exceed the nameplate percentages below:

a.	Distribution Transformers	130% winter; 100% summer
b.	Regulators	130% winter; 100% summer
•	Step Voltage Transformers	130% winter; 100% summer
C.	_	80% winter; 80% summer
d.	Reclosers	80% winter; 80% summer
e.	Line Fuses	80% WILLEI, 80% Sullinei

- 4. Conversions to multiphase are to correct voltage drop and phase balance. Line sections operating at 12.5/7.2 kV with load currents exceeding 40 amps, 24.9/14.4 kV lines with load currents exceeding 35 amps and lines sections with greater than 60 customers will be considered for multiphasing. Operating and engineering practices used to develop the loading criteria are based on a single phase line interruption that may cause operation of the ground trip relay on three phase oil circuit reclosers.
- 5. Three phase tie points between substations should be equipped with air break switches.
- 6. Conductors and associated poles and hardware will be considered for replacement if any of the following conditions exist:
 - a. More than 3 outages or 10 outage hours per year excluding major storms and power supplier for two out of the past three years.
 - b. Conductors with an average of greater than one splice per phase per span in one mile increments.
 - c. Ordinary replacement of old, deteriorated conductor on a systematic basis.
 - d. A significant amount of load that is served by aged, faulty conductor will be considered for refeeding if a more efficient route on existing right of way can be found.

Shelby CWP: II-A1

Page 2

Poles and/or crossarms to be replaced if found to be physically deteriorated by visual inspection or testing.

8. Standard conductor sizes evaluated by economic conductor analysis. The standard conductor sizes include the following:

OVERHEAD #2 ACSR UNDERGROUND

1/0 ALUG

1/0 ACSR

4/0 ALUG

4/0 ACSR and 336.4 ACSR

- 9. All new primary construction is to be overhead except where underground conductor is required to comply with governmental or environmental regulations, local restrictions, design necessities, or favorable economics.
- 10. All new construction is to be designed and built according to RUS standard construction specifications and guidelines.
- Capacitors placed on the system to maintain 90% power factor during system peak with an emphasis on correction to 95% correction as economics dictate.
- 12. Conductors and associated poles and hardware will be rebuilt or relocated if they present a potential hazard, are found to be unsafe, or fail to meet the applicable NESC requirements.
- Consider the installation of dual voltage, 7.2 X 14.4 kV transformers on all new construction in areas that are designated for voltage conversion within the next load block of the Long Range System Plan.
- 14. Adjoining substations should have reserve capacity equal to the peak projected load transfer between them.
- All substations should be equipped with a low-side bypassing scheme that will allow any given circuit recloser to be bypassed for maintenance while an adjacent recloser feeds the circuit through the bus system.
- 16. New substations metering should be equipped with a bypassing mechanism.
- 17. EKP member distribution cooperatives and other foreign utility interconnections should be considered in fringe areas of the system as an alternative to other types of present and future system improvements. This will be coordinated through East Kentucky Power.

ITEM #33 EXHIBIT "A" PAGE 3 OF 22

Shelby CWP: II-A1 Page 3

- A transmission loop through the system should be continuously evaluated based on developing loads and historical power supplier outage data. This will be evaluated with East Kentucky Power.
- 19. Per the NESC requirements, idle services shall be maintained or retired. Services that have been idle for more than two years should be evaluated for future use. If no use is foreseen, the service should be retired.
- Fused cutouts and lightning arresters should be added to all existing CSP transformers on the three phase portion of the system between the substation and the first set of downline circuit reclosers.
- All single phase taps that are between a three phase circuit recloser and the first set of downline, single-phase reclosers should be fused.
- 22. All outgoing conductor from 12 kV substations will be 336 ACSR or larger. All outgoing conductor from 25 kV substations will be 4/0 ACSR or larger.
- When a new substation is constructed or a second substation transformer is placed in an existing substation site, additional circuits will be needed in order to adequately distribute the new and/or additional substation capacity.

FINANCIAL CRITERIA

- > Cost of Capital = 4.98%
- \triangleright Inflation = 3.5%
- > Compound Annual Load Growth = 6.0%
- > Increase in Cost of Power = 2.8%
- > Present Worth Discount Factor = 4.98%
- > Depreciation = 3.08%
- > 0 & M = 4.87%
- > Tax & Ins = 1.15%
- > TOTAL ANNUAL FIXED CHARGE RATE = 14.08%

Shelby CWP: II-A2

Page 1

SYSTEM CRITERIA DEFICIENCIES

SUBSTATION Logan I	CIRCUIT 3	SECTION 727	DEFICIENCY #	CORRECTIVE ACTION Convert to 3ph 1/0 conductor.
Logan I	4	451-455	1	Add 3 voltage regulators (VR) to 462.
Clayvillage	3	369, 374,128	1 and 4	Vph 1.1 mi of 128 and Vph 375 and 897 and refeed sections 374 and 369.
Clayvillage	4	414-417	1	Add (1) VR on 417 defer Vph conv.
New Castle	1	244-251	1	Add (2) VRs on 141.
New Castle	2	826, 273, 277	1	Move (2) VRs from 827 to 826 (add 3rd).
New Castle	2	295	1	Add (1) VR on 297.
New Castle	3	333	1 and 4	3ph 2ACSR 333.
Campbellsburg	1	208-210, 212 765, 211-214	1 and 4 "	Vph 2ACSR 210, refeed 211 from 212 and add (1) VR on 766.
Campbellsburg	2	139-141	1	Add (1) VR on 141.
Campbellsburg	2	238-240 & 861	1	Add (1) VR on 243.
Campbellsburg	2	129, 131, 136	1	Add (1) VR on source of 131.
Bedford	1	49	1 and 4	Vph 2ACSR 1.1 mi of 49.
Bedford	1	55-57, 62	1 and 4	3ph 1/0ACSR 62 & 63, Vph 2ACSR 747' refeed 61 to relieve 65.
Bedford	4	99-101	1	Refeed from 98 out of Milton Sub.
Bedford	4	80-84	1	Add (3) VRs on 635.
Milton .	4	28 & 30	4	No changes made. Discussed with Operations and no problems with overload.
Bekaert I & II	3 & 5	955, 956, 957 & 960	23	Build 0.6 miles of DCT Bundled 4/0 conductor and 0.6 miles of single CKT Bundled 4/0 conductor both on existing structures to distribute the Bekaert II capacity upgrade.

Shelby CWP: II-A2

Page 2

SUBSTATION Jericho	CIRCUIT 1	<u>SECTION</u> 179, 166, 180	DEFICIENCY #	CORRECTIVE ACTION Add (3) VRs to 796.
Jericho	1 & 2	964 & 965	23	Convert 1.0 mile to 336 ACSR DCT out of Jericho sub toward toward the Pendleton load center.
Jericho	3	320 & 821	22	Build 1 mile of 336 ACSR along with the above VR on 796 and defer 8 miles of 336 ACSR construction. This will begin a 336 link between Jericho & Logan L

^{*}NOTE: Category 6 deficiencies are outlined in the Cost Summary. They are discussed in the Aged Plant Report in section III-G.

ITEM #33 EXHIBIT "A" PAGE 6 OF 22

SHELBY CWP: II-A

Page 1

DISTRIBUTION SYSTEM DESIGN CRITERIA 2001 - 2004 CWP Each of the following criteria items were reviewed and accepted by the RUS General Field Representative on October 19, 2000.

- 1) The minimum voltage on primary distribution lines is 118 volts (120 volt base, 126 volts at source) after re-regulation. Cascading of distribution voltage regulators is not an acceptable improvement.
- 2) Primary conductors are not to be loaded over 75% of their thermal rating.
- 3) The following equipment will not be thermally loaded by more than the percentage shown:

a) Distribution Transformers 130% winter, 100% summer 130% winter, 100%

- 4) Conversions to multiphase are to correct voltage drop and phase balance. Line sections operating at 12.5/7.2 kV with load currents exceeding 45 amps will be considered for multiphasing. 24.9/14.4 kV lines with load currents exceeding 40 amps will be considered for multiphasing. Line sections with greater than 60 customers will be considered for multiphasing. Operation and engineering practices used to develop the loading criteria are based on a single phase line interruption that may cause an operation of the ground trip relay on three phase oil circuit reclosers.
- 5) Three phase tie points between substations should be equipped with air break switches.
- 6) Conductors and associated poles and hardware will be considered for replacement on a priority basis as defined below:
 - 1 Replace all 8 ACWC.
 - 2. Replace 6 ACWC and #4 ACSR.
 - 3. URD cable as needed.
- 7) Poles and/or crossarms are to be replaced if found to be physically deteriorated by visual inspection or testing.

ITEM #33 EXHIBIT "A" PAGE 7 OF 22

SHELBY CWP: II-A Page 2

- 8) Primary distribution lines are to be rebuilt and/or relocated if they are found to be unsafe or fail to meet applicable National Electric Safety Code standards.
- 9) All new construction is to be designed and built according to RUS standard construction specifications and guidelines.
- 10) Capacitors are placed on the system to maintain 90% power factor during system peak with and emphasis on correction to 95% as economics dictate.
- 11) New primary conductor sizes are to be determined on a case by case basis using the Economic Conductor Analysis method. The proposed conductor sizes may be modified to conform to the cooperative's standard sizes and recommendations of the Long Rang Plan. The standard Overhead conductor sizes are #2 ACSR, 1/0 ACSR, 4/0 ACSR and 336.4 ACSR. The standard Underground conductor sizes are 1/0 ALUG, 4/0 ALUG, and 500 MCM ALUG.
- 12) Substation feeders will be limited to a 250 amp loading level. Feeders reaching this limit shall have load switched or an additional substation feeder will be installed.
- 13) All outgoing feeders from 12.5 kV substations will be 4/0 ACSR or larger. All outgoing feeders from 25 kV substations will be 4/0 ACSR or larger.

ITEM #33 EXHIBIT "A" PAGE 8 OF 22

2005 Work Plan

Shelby Energy Cooperative, Inc. Shelbyville, Kentucky

Add	<u>ditions to Distribution Plant - 2005</u>			2005		Percent
A.	New Member Extensions Residential and Commerical Customers Distribution Transformers Meters and Meter Sockets	Quantity 500 350 500	\$2,000 550 60	Estimate \$1,000,000 192,500 30,000	\$1,222,500.00	of Total
B.	Increased Service Capacity Service and Secondary Upratings Distribution Transformers	50 125	1,000 550	50,000 68,750	\$118,750.00	4.11%
C.	Poles Added for Clearance and Reliabi Poles	25	1,100	27,500	\$27,500.00	0.95%
D.	Line Conversions, Conductor Replace See Next Page for Details	ments and	Feeder Reh	abs 1,231,985	\$1,231,985.00	42.66%
E.	Ordinary Replacements Pole Changes	90	1,400	126,000		
F.	Other Equipment Security Lights Single Phase Oil Circuit Recloser (OCR) Fused Cutouts & Lightning Arresters SCADA	120 20 100 4	2,000 250	48,000 40,000 25,000 48,000	\$126,000.00 \$161,000.00	4.36% 5.58%
To	otal Additions to Distribution Plant - 200	<u>5</u>			\$2,887,735.00	100.00%

Project	Line Section(s)	Substation	Total	Description	Total Est. Cost	Comments
	7.4.7		1 00	1 Ph /2 Ph. Conversion-#2 ACSR	27,700.00	Figgs Store Rd. Shelby (C/O fm 03)
	11.		09:0	1 Ph /2 Ph Conversion-#2 ACSR	16,620.00	Locust Grove Rd. Shelby (C/O fm 03)
	4/3		7.00	1 Ph Conductor Rolemt -#2 ACSR	27,750.00	Locust Grove Rd. Shelby (C/O fm 03)
	4/3		2.10	1 Ph. Conductor Rolemt -#2 ACSR	38,850.00	Donahue&HaleyRd. Shelby (C/O fm 03)
	4/0		3.00	1 Ph /2 Ph. Conversion-#2 ACSR	85,500.00	KY Hwy. 148W, Fisherville Rd. Shelby
320	408 303	C-Village	09.0	1Ph./ 2Ph. Conversion-#2 ACSR	17,100.00	Christianburg-Cropper Rd. Shelby
	341 340		1.70	1 Ph. Conductor Rplcmt#2 ACSR	32,300.00	Moody Pike Shelby
	364		2.50	1 Ph. Conductor Rplcmt#2 ACSR	47,500.00	KY Hwy. 395N, Elmburg Rd. Shelby
	757		1.20	1 Ph.Conductor Rpicmt#2 ACSR	22,800.00	Bob Rogers Rd. Shelby
	101		3.40	1 Ph. Conductor Rolcmt, -#2 ACSR	64,600.00	Vigo Rd., Consolation to Hatton Shelby
	300		3.60	3 Ph. Circuit Rehab. #2 CU	36,000.00	KY55N-KY316, Providence, Henry&Trimble
	252, 253		5 5	1	42,000,00	Orem Lane Henry
	150, 153, 154, 158		4.20	S TII, OII CUIL IRBII AD # A OO	14,000.00	Description of Trimble (C/O fm)
	234		2.00	1 Ph. Conductor Rplcmt#2 ACSR	37,000.00	Providence-Louden Rds, Trimble (C/O IIII o
	45 59		7.50	1 Ph. Conductor Rplcmt#2 ACSR	142,500.00	Mt. Herman Ch.&Wrights Ridge Kds. Trimb
	, co		4.30	1 Ph. Conductor Rplcmt#2 ACSR	79,550.00	Backcreek Rd. Shelby (C/O fm 03)
	200		1.40	1 Ph. Conductor Rolemt#2 ACSR	26,600.00	Hinkle Ln. Shelby
	449	_	2		00 070 007	Destricted to Catridge Shelly (C/O fm 03)
	548, 504499	Southville	9.30	1 Ph. & 2 Ph. Cond. Kplmt#2 ACSK	188,010.00	realinge to cathogo cheby (0/0 iiii co)
TOTALS:	.s:		49.90	miles	\$932,980.00	

D. Line Conversions/Conductor Replacements - RUS Code 300

2005 Work Plan

All projects listed herein are carried over from prior years of 2001-2004 four-year Construction Work Plan. 'A' Denotes amendment to Construction Work Plan

ITEM #33 EXHIBIT "A" PAGE 10 OF 22

2004 Work Plan

Shelby Energy Cooperative, Inc. Shelbyville, Kentucky

<u>Ad</u>	ditions to Distribution Plant - 2004					
				2004		Percent
A.	New Member Extensions	Quantity	Cost/Unit	Estimate		of Total
	Residential and Commerical Customers	500	\$2,000	\$1,000,000		
	Distribution Transformers	275	650	178,750		
	Meters and Meter Sockets	500	60	30,000		
					\$1,208,750.00	36.81%
₿.	Increased Service Capacity					
	Service and Secondary Upratings	50	1,000	50,000		
	Distribution Transformers	150	650	97,500		
					\$147,500.00	4.49%
C.	Poles Added for Clearance and Reliabi	ility Initiativ	e .			
	Poles	100	1,100	110,000		
					\$110,000.00	3.35%
D.	Line Conversions, Conductor Replace	ments and	Feeder Reha	abs		
	See Next Page for Details	•		1,567,305		
					\$1,567,305.00	47.72%
E.	Ordinary Replacements					
,	Pole Changes	150	450	67,500		
	C					
					\$67,500.00	2.06%
F.	Other Equipment					
	Security Lights	150	300	45,000		
	Single Phase Oil Circuit Recloser (OCR)	20	2,000	40,000		
	Fused Cutouts & Lightning Arresters	200	250	50,000		
	SCADA	4	12,000	48,000		
					\$183,000.00	5.57%
<u>T</u> c	otal Additions to Distribution Plant - 200	<u>4</u>			\$3,284,055.00	100.00%

Comments	Figgs Store Rd. Shelby (C/O fm 03)	Locust Grove Rd. Shelby (C/O fm 03)	Locust Grove Rd. Shelby (C/O fm 03)		KY Hwy, 148W, Fisherville Rd. Shelby	per Rd. Shelby	Moody Pike Shelby	KY Hwy. 395N, Elmburg Rd. Shelby	Bob Rogers Rd. Shelby	Vigo Rd., Consolation to Hatton Shelby	KY55N-KY316, Providence, Henry&Trimblej	Orem Lane Henry	Providence-Louden Rds. Trimble (C/O fm v3)	Perkison LnBareboneRd. Trimble (C/O fm 03)	Colbert Ln. Trimble	Cutshaw Ln. Trimble	Pryors Fork Rd. to Mullican Ln. Trimble	Mt. Herman Ch.&Wrights Ridge Rds. Trim իլ ի	Backcreek Rd. Shelby (C/O fm 03)	KY Hwy, 395-Catridge Rd. Shelby (C/O fnrd3)	Catridge Rd. S & KY Hwy. 53S Shelby	Hinkle Ln. Shelby	_	Harington Mill-BurksBranch Rds. Shelby	
Total	27,700.00	16,620.00	27,750.00	38,850.00	85,500.00	1.7,100.00	32,300.00	47,500.00	.22,800.00	64,600.00	36,000.00	42,000.00	37,000.00	129,500.00	38,000.00	11,400.00	28,500.00	142,500.00	79,550.00	68,450.00	57,000.00	26,600.00	188,610.00	301,475.00	\$1,567,305.00
Description	1 Ph./2 Ph. Conversion-#2 ACSR	1 Ph./2 Ph. Conversion-#2 ACSR	1 Ph.Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph./2 Ph. Conversion-#2 ACSR	1Ph./ 2Ph. Conversion-#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph.Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplomt#2 ACSR	3 Ph. Circuit Rehab#2 CU	3 Ph. Circuit /Rehab#2 CU	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt,-#2 ACSR	1 Ph, Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. & 2 Ph. Cond. Rplmt#2 ACSR	3 Ph. Conv. w/12kV to 25kV Conv.	miles \$
Total	Length 1.00	09.0	1.50	2.10	3.00	09.0	1,70	2:50	1.20					7.00			1.50	7.50		3.70	3.00	1,40	9.30	8.00	75.70
Substation	Logan 1	Logan 1	Logan 1	Logan 1	Logan 1	C-Village	C-Village	C-Village	C-Village	C-Village	C-Burg	C-Burg	C-Burg	Bedford	Bedford	Bedford	Bedford	Bedford	Southville	Southville	Southville	Logan 2	Southville	Logan/Cvlg	
Project Line Section(s)	No. 31 5* 477	316* 473	116* 473		20 489	22 393		127 364			32* 232, 235		234	340* 90, 91, 92	341 912		366 124		506	349* 500				369A 879349	TOTALS:
۵	Z'n	دب	ىن	က်	က	t,	c,	က်	က	E.	m	m	m	ကိ	, e.	ű	ຕ	بن	, ų	يى	က်	ကိ	m	G	—

D. Line Conversions/Conductor Replacements - RUS Code 300

2004 Work Plan

Project carried over from prior year of 4 year Construction Work Plan, 2001, 2002 or 2003
 'A' Denotes amendment to Construction Work Plan

2003 Work Plan

Shelby Energy Cooperative, Inc. Shelbyville, Kentucky

Add	ditions to Distribution Plant - 2003			2003		Percent
A.	New Member Extensions Residential and Commerical Customers Distribution Transformers Meters and Meter Sockets	Quantity 500 275 500	Cost/Unit \$2,000 650 60	Estimate \$1,000,000 178,750 30,000		of Total
					\$1,208,750.00	43.24%
В.	Increased Service Capacity Service and Secondary Upratings Distribution Transformers	50 150	1,000 650	50,000 97,500	\$147,500.00	5.28%
C.	Poles Added for Clearance and Reliable	ility Initiativ	re		,	
	Poles	100	1,100	110,000	\$110,000.00	3.93%
D.	Line Conversions, Conductor Replace See Next Page for Details	ments and	Feeder Reh	abs 1,087,715	\$1,087,715.00	38.91%
E.	Ordinary Replacements Pole Changes	150	450	67,500		
					\$67,500.00	2.41%
F.	Other Equipment Security Lights Single Phase "Oil Circuit Recloser (OCR) Three Phase OCR w/ controls SCADA	150 30 2 4	2,000 10,500	21,000	\$174,000.00	6.22%
<u>T</u> 0	otal Additions to Distribution Plant - 200	<u>)3</u>			\$2,795,465.00	100.00%

:						ITE	EM #	¹ 33	EX	HIB:	IT "/	45°	P	Ö ÆGE	E 13	OF 2	22	Ö		· o	
	Comments	Figgs Store Rd. She;by Co.	Locust Grove Rd. Shelby Co.	Locust Grove Rd. Shelby Co.	Donahue & Haley Rd. Shelby Co.	Noland Rd. to Webb Rd. Shelby Co.	Beechridge Rd. to Hatton Shelby Co.	Benson Rd. Shelby Co.	Ridgemore Mansion Shelby Co.	Pt. Pleasant to Russell Br. Henry Co.	Providence-Louden Rd. Trimble Co.	Turkey Run to Long Branch Rd. Henry	Perry Park Air Strip Owen Co.	Perkison, Harley & Bearbone Rds. Trimbe Co.	Hempridge Rd. Shelby Co.	Back Creek Rd. Shelby Co.	Harrisonville HWY 395 Shelby Co.	Pecks Pike to Rodgers Rd. Trimble Co.	Long Run Woods Shelby Co.	Dr. Holmes Tap Brooks Ln. Shelby Co.	
300	Total Fet Cost	27,700.00	16,620.00	27,750.00	38,850.00	72,020.00	82,800,00	97,500.00	26,600.00	113,400.00	37,000.00	87,875.00	26,600.00	129,500.00	69,000.00	79,550.00	68,450.00	58,500.00	18,800.00	9,200.00	\$1,087,715.00
D. Line Conversions/Conductor Replacemes - RUS Code 300	Description	1 Ph./2 Ph. Conversion-#2 ACSR	1 Ph./2 Ph. Conversion #2 ACSR	1 Ph.Conductor Rplcmt. #2 ACSR	1 Ph. Conductor Rplcmt. #2 ACSR	1 Ph./2 Ph. Conversion-#2 ACSR	1Ph./ 3Ph. Conversion-#2 ACSR	3 Ph. Dbl. Crt. #2 to 336.4 ACSR	3 Ph. UG Cond. Rplcmt1/0 AL	1 Ph.Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt#2 ACSR	1 Ph. Conductor Rplcmt. #2 ACSR	3 Ph. UG Cond. Rpicmt1/0 AL	1 Ph. Conductor Rplcmt. #2 ACSR	3 Ph./3 Ph. #2 to 4/0 ACSR	1 Ph. Conductor Rplcmt. #2 ACSR	1 Ph. Conductor Rplcmt. #2 ACSR	1 Ph./3 Ph. Conversion-1/0 ACSR	1 Ph. UG Cond. Rplcmt1/0 AL	1 Ph. UG Cond. Rplcmt1/0 AL	miles
ersions/C	Total	Length 1.00	09'0	1.50	2.10	2.60	2.40	1.30	0.20	6.30	2.00	4.75	0.20	7.00	1.50	4.30	3.70	1.50	0.40	0.20	43.55
D. Line Conv	Substation	Logan 1	Logan 1	Logan 1	Logan 1	Logan 1	C-Village	C-Village	C-Village	New Castle	C-Burg	C-Burg	C-Burg	Bedford	Southville	Southville	Southville	Milton	Long Run	Long Run	
2003 Work Plan	Line Section(s)	477	473	473	476	437, 732	849, 370, 372	404, 545	3 Ph. UG Tap RM	300, 302	234	220, 224	3 Ph. UG Tap PP	90, 92	517	506	200	20, 96, 98	Long Run Woods	1 Ph. UG Tap	
2003 W	Project #	315	316	316	317	355	323*	324	363*	330*	334	335*	362*	340	346*	348	349	351	360	361	TOTALS:

* Project carried over from prior year of 4 year Construction Work Plan, 2001 or 2002

2002 Work Plan

Shelby Energy Cooperative, Inc. Shelbyville, Kentucky

Ado	litions to Distribution Plant - 2002			2001		Percent
	New Member Extensions Residential and Commerical Customers Distribution Transformers Meters and Meter Sockets	Quantity 500 275 500	\$2,000 650 60	Estimate \$1,000,000 178,750 30,000	\$1,208,750.00	of Total 43.61%
В.	Increased Service Capacity Service and Secondary Upratings Distribution Transformers	50 150	1,000 650	50,000 97,500	\$147,500.00	5.32%
C.	Poles Added for Clearance and Reliab Poles	ility Initiativ 50	700	35,000	\$35,000.00	1.26%
D.	Line Conversions, Conductor Replace See Next Page for Details	ments and	Feeder Reh	abs 1,062,160	\$1,062,160.00	38.33%
E.	Ordinary Replacements Pole Changes	150	1,100	165,000		
- -	Other Equipment				\$165,000.00	5.95%
F.	Other Equipment Security Lights Oil Circuit Reclosers SCADA	150 30 4	2,000	45,000 60,000 48,000	\$153,000.00	5.52%
I	otal Additions to Distribution Plant - 200	02	-		\$2,771,410.00	100.00%

ITEM #33 EXHIBIT "A" PAGE 15 OF 22 2002 Work Plan D. Line Conversions/Conductor Replacements - RUS Code 300

CRF Code	County	Substation	Sect. No.	Description	Calegory	Miles	Cost/Mi.	Extended Cost
323	Shelby	Clay Village	849 370	1 Ph. #2 ACSR to 3 Ph. #2 ACSR	Conversion			
			372			2.4	34,500	82,800.00
329	Henry	New Castle	333	1Ph. #2 ACSR to 3 Ph. #2 ACSR	Conversion	3.1	30,000	93,000.00
330	Henry	New Castle	300 302	1 Ph. 6A CWC to 1 Ph. #2 ACSR	Replacement			
331	Henry	Campbellsburg	194 196	#2 CU Rehabilitation	Reháb	6.3	18,000	113,400.00
			852			5.3	10,000	53,000.00
332	Henry	Campbellsburg	232 235	#2 CU Rehabilitation	Rehab			
335	Henry	Campbellsburg	224	1 Ph. 6A CWC to 1 Ph. #2 ACSR	Replacement	3.6	10,000	36,000.00
			222			. 3.0	18,000	54,000.00
337	Trimble	Bedford	745 . 116	1Ph. 6A CWC to 3 Ph. #2 ACSR	Conversion			
			117			2.2	35,500	78,100.00
339	Trimble	Bedford	725	1 Ph. 6A CWC to 1 Ph. #2 ACSR	Replacement	2.1	18,000	37,800.00
344	Shelby	Southville	534 538	3 Ph. #4 ACSR to 3 Ph. 4/0 ACSR	Conversion			
			539			3.0	47,380	142,140.00
346	Shelby	Southville	517	3 Ph. #4 ACSR to 3 Ph. 4/0 ACSR	Conversion	1.5	47,380	71,070.00
347	Shelby	Southville	510 511	1 Ph. 6A CWC to 3 Ph. #2 ACSR	Repalcement	t		
352	Trimble	Milton	413 9	1 Ph. 6A CWC to 1 Ph. #2 ACSR	Replacemen	2.5 t	34,500	86,250.00
	, , , , , ,	· · · · · · · · · · · · · · · · · · ·	11			2.9	9 18,000	52,200.00
354	Shelby	Logan East	465	1 Ph. #4 ACSR to 1 Ph. #2 ACSR	, Replacemen	it 3.6	000,81	54,000.00
361	Shelby	Long Run	Тар	1 Ph. URD Cable Replacement	Replacemer	nt 0.:	2 46,000	9,200.00
362	Owen	Campbellsburg	ј Тар	3 Ph. URD Cable Replacement	Replacemer	nt 0	2 133,000	26,600.00
363	Shelby	Clay Village	Тар	3 Ph. URD Cable Replacement	Repalcemer	nt O.	2 133,000	26,600.00
-	Shelby	Logan East	Тар	1 Ph. URD Cable Replacement	Replacemen	nt 1.	0 46,000	46,000.00
Totals.	;					42.	5	\$1,062,160.00

2001 Work Plan

Shelby Energy Cooperative, Inc. Shelbyville, Kentucky

Ado	<u>litions to Distribution Plant - 2001</u>			2001		Percent
A.	New Member Extensions Residential and Commerical Customers Distribution Transformers Meters and Meter Sockets	Quantity 500 275 500	\$2,200 650 60	Estimate \$1,100,000 178,750 30,000	\$1,308,750.00	of Total 59.86%
В.	Increased Service Capacity Service and Secondary Upratings Distribution Transformers	50 150	1,000 650	50,000 97,500	\$147,500.00	6.75%
C.	Poles Added for Clearance and Reliabi Poles	lity Initiativ 100	r e 1,100	110,000	\$110,000.00	5.03%
D.	Conversions and Tie Lines See Next Page(s) for Details			28,930	\$28,930.00	1.32%
E.	Ordinary Replacements Pole Changes Ordinary Conductor Replacements, See Next Page(s) for Details	150	450-	67,500 418,500	4400 000 00	22 229/
F.	Other Equipment Security Lights Oil Circuit Reclosers	150 30			\$486,000.00 \$105,000.00	22.23% 4.80%
Ιs	otal Additions to Distribution Plant - 200	1			\$2,186,180.00	100.00%

2001 Work Plan
D. Conversions and Tie-Lines

	28,930.00	28,930.00
Extended Cost	28,930.00	
Cost/Mi.	1.10 26,300.00	
Miles	1.10	1.10
Description	1 Ph. 6A CWC to V Ph. #2 ACSR	
Sect. No.	49	
CRF County Sect. Code No.	1 Sub Carroll Subtotals:	
CAP	311 Bedford Sub Carro Subfot	Totals

2001 Work Plan
E. Ordinary Conductor Replacements

CRF Code	County	Sect. No.	Description	l Miles	New Installed O. Cost/Mi. Cc	Original Cost/Mi.	Net Cost/Mi.	Extended Cost	
Clay Village Sub 606.1 Shelb	age Sub Shelby	352 350	3Ph. #2 ACSR to 3Ph. 336.4 KCM ACSR 3Ph. #2 ACSR to 3Ph. 336.4 KCM ACSR	3.00	\$40,000.00 40,000.00		40,000.00	120,000.00 16,000.00	ITEM
	Subtotals:			3.40			_		\$136,000.0
Campbel 606.11	Campbellsburg Sub 606.11 Henry	224 223 222	1Ph. 8A CWC to 1Ph. #2 ACSR " " "	3.20 0.90 0.70	\$12,500.00 12,500.00 12,500.00		12,500.00 12,500.00 12,500.00	40,000.00 11,250.00 8,750.00	EXH
		221 220 744	= = =	2.00	12,500,00 12,500.00 12,500.00		12,500.00 12,500.00 12,500.00	25,000.00 22,500.00 10,000.00	IBIT '
	Subtotale:	142		0.40	12,500.00 12,500.00 12,500.00		12,500.00	30,000.00	"A" 00 00 °C
	ouniciais.			4 : 4 :					
Southville Sub 606.18 She	l e Sub Shelby	510 510 413 412 898	1Ph. 8A CWC to 1Ph. #2 ACSR " " " " " "	1.70 1.60 0.70 1.30 2.80 0.90	12,500.00 12,500.00 12,500.00 12,500.00 12,500.00		12,500.00 12,500.00 12,500.00 12,500.00 12,500.00	21,250.00 20,000.00 8,750.00 16,250.00 35,000.00	PAGE 18 OF
	Subtotals:	! !		9.00					\$112,500.00
1	Replacement of Phasesectionalizing device	of Pha device	Replacement of Phase Conductor from main feeder to first tap line sectionalizing device	2.50	7,000.00		7,000.00	17,500.00	\$17,500.00
Totals:				27.10	•				\$418,500.00

ITEM #33 EXHIBIT "A" PAGE 19 OF 22

2000 Work Plan

Shelby Energy Cooperative, Inc. Shelbyville, Kentucky

1154	and to blandalon hanc 2000			0000				
			•	2000	•			
Α.	New Member Extensions	Quantity	Cost/Unit	Estimate				
	Residential and Commerical Customers	550	\$1,800	\$990,000				
	Distribution Transformers	300	600	180,000				
	Meters and Meter Sockets	550	80	44,000	•			
				,	\$1,214,000.00			
В.	Increased Service Capacity							
	Service and Secondary Upratings	50	630	31,500				
	Distribution Transformers	150	690	103,500				
		,	000	100,000	\$135,000.00			
C.	Poles Added for Clearance and Reliabi	lity Initiativ			Ψ135,000.00			
٥.	Poles	-		400.000				
	rules	100	1,000	100,000	0402.000.00			
_					\$100,000.00			
D.	Conversions and Tie Lines				•			
	See Next Page(s) for Details			151,460				
	•				\$199,690.00			
E.	Ordinary Replacements							
	Pole Changes	150	450	67,500				
	Ordinary Conductor Replacements,			250,000				
	See Next Page(s) for Details			,				
	•				\$317,500.00			
F.	Other Equipment				,,,			
	Security Lights	150	220	33,000				
	Oil Circuit Reclosers	30	2,000	60,000				
		00	2,000	00,000	\$93,000.00			
					433,000.00			
Total Additions to Distribution Plant - 2000 \$2,059,190,00								
	\$2,053,150.00							

2000 Work Plan
D. Conversions and Tie-Lines

	-	\$37,200.00			\$85,330.00		28,930.00	48,230.00
Extended Cost	\$37,200.00		10,560.00	7,890.00		28,930.00		10,600.00 37,630.00
Cost/Mi.	\$62,000.00		35,200.00	33,290.00 26,390.00		26,300.00	·	53,000.00 53,000.00
Miles	0.60	0.60		08.0	2.60	1.40	1.10	0.20
Seçt. Description No.	727 1 Ph. #4 AÇSR to 3 Ph. 1/0 Aerial Cable		1 Ph. 6A CWC to 3 Ph. 1/0 ACSR	1 Ph. 6A CWC to V Ph. #2 ACSR		1 Ph. 6A CWC to V Ph. #2 ACSR		3 Ph. 4/0 Aerial Cable, Dbl. Çir., New Const. 3 Ph. 4/0 Aerial Cable, Add'l Cir.
Sect. No.	727		62	747		49	5	425
County	sub Shelby	Subtotals;	d Sụb Trìmble		Subtotals;	d Sub Carroll	S <i>ubtotąls;</i> un Sub (Nev	shelby * 4 Subtotals:
CRF Code 305	Logan Sub St	309	Bedford Sμb Triπ		311	Bedford Sub	3 314 Long Ru) ·

*Third circuit out of Long Run Substation is optional and may not be constructed at this time. The cost is included in budget in the event that this option is exercised.

Totals:

199,690.00

5.11

2000 Work Plan E. Ordinary Conductor Replacements

14,556.00 26,686.00 14,556.00	EX 00.354.00\$	98,760.00 13,168.00	\$111,928.00 %	PAGE 94.7,718.00	21 OF 00.000,000,000,000,000
**		32,920.00 32,920.00			
\$2,700.00 \$2,700.00 \$2,700.00 \$2,700.00		\$7,989.00 \$7,989.00			
\$26,960.00 \$26,960.00 \$26,960.00 \$26,960.00		\$40,000.00 \$40,000.00			
0.60 1.10 0.60 0.60	2.90	3.00	3.40		6,30
V Ph. #2 AÇSR to 3 Ph. 1/0 ACSR V Ph. #2 ACSR to 3 Ph. 1/0 AÇSR V Ph. #2 AÇSR to 3 Ph. 1/0 AÇSR V Ph. #2 ACSR to 3 Ph. 1/0 AÇSR		3Ph. #2 ACSR to 3Ph. 336.4 KCM ACSR 3Ph. #2 ACSR to 3Ph. 336.4 KCM ACSR		nase Conductor from main feeder to first tap line ce	
532 529 526 906		352 350		nt of Ph ng devic	
Southville Sub 606.26 Shelby "	Subtotals:	Clay Village Sub 606.1 Shelby	Subtotals:	System-Wide - Replacemer sectionalizir	Totals:
	by 532 VPh. #2 AÇSR to 3 Ph. 1/0 ACSR 0.60 \$26,960.00 \$2,700.00 \$24,260.00 \$14,556.00 529 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 0.60 \$26,960.00 \$2,700.00 \$4,260.00 26,686.00 526 VPh. #2 AÇSR to 3 Ph. 1/0 AÇSR 0.60 \$26,960.00 \$2,700.00 \$4,260.00 14,556.00 906 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 0.60 \$26,960.00 \$2,700.00 \$24,260.00 14,556.00	by 532 VPh. #2 ACSR to 3 Ph. 1/0 ACSR 0.60 \$26,960.00 \$24,260.00 \$14,556.00 1.10 \$26,960.00 \$24,260.00 \$6,686.00 26,686.00 256 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 0.60 \$26,960.00 \$2,700.00 24,260.00 14,556.00 906 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 0.60 \$26,960.00 \$2,700.00 24,260.00 14,556.00 14,556.00 14,556.00 2.90	532 V Ph. #2 AÇSR to 3 Ph. 1/0 ACSR 529 V Ph. #2 ACSR to 3 Ph. 1/0 AÇSR 529 V Ph. #2 ACSR to 3 Ph. 1/0 AÇSR 526 V Ph. #2 ACSR to 3 Ph. 1/0 AÇSR 906 V Ph. #2 ACSR to 3 Ph. 1/0 AÇSR 529 V Ph. #2 ACSR to 3 Ph. 1/0 AÇSR 906 V Ph. #2 ACSR to 3 Ph. 1/0 AÇSR 907 \$2,700.00 \$4,260.00 \$14,556.00 \$14,556.00 \$24,260.00 \$14,556.00 \$24,260.00	532 VPh. #2 AÇSR to 3 Ph. 1/0 ACSR 529 VPh. #2 ACSR to 3 Ph. 1/0 ACSR 529 VPh. #2 ACSR to 3 Ph. 1/0 ACSR 529 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 520 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 520 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 520 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 520 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 520 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 520 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 520 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 520 VPh. #2 ACSR to 3 Ph. 1/0 AÇSR 520 VPh. #2 ACSR to 3 Ph. 336.4 KCM ACSR 520 VPh. #2 ACSR to 3 Ph. 336.4 KCM ACSR 520 VPh. #2 ACSR to 3 Ph. 336.4 KCM ACSR 530 VPh. #2 ACSR to 3 Ph. 336.4 KCM ACSR 530 VPh. #2 ACSR to 3 Ph. 336.4 KCM ACSR 530 VPh. #2 ACSR to 3 Ph. 36.4 KCM ACSR 530 VPh. #2 ACSR to 3 Ph. 760 VPh. 760 V	10 529 V Ph. #2 ACSR to 3 Ph. 1/0 ACSR 0.60 \$26,960.00 \$2,700.00 \$24,260.00 \$14,556.00 1.10 \$26,960.00 \$2,700.00 \$24,260.00 \$14,556.00 26,686.00 5.20 V Ph. #2 ACSR to 3 Ph. 1/0 ACSR 0.60 \$26,960.00 \$2,700.00 \$24,260.00 \$14,556.00 14,556

ITEM #33 EXHIBIT "A" PAGE 22 OF 22 Shelby Energy Cooperative, Inc. Projected Distribution Plant Replacement/Improvement Budget

YEAR	BUDGET	
	AMOUNT	•
2005	\$1,357,985. O	(A ctual)
2006	1,400,000.00	(Projected)
2008	1,450,000.00	
2009	1,450,000,🔾 🔾	
2010	1,500,000.🔾	
2011	1,500,000.⊖ ⊙	
2012	1,550,000. ○○	
2013	1,550,000.🔾	
2014	1,600,000. ○○	•
2015	1,600,000. OO	
2016	1,650,000.00	
2017	1,650,000.00	
2018	1,700,000.00	
2019	1,700,000.00	
2020	1,750,000.0	
2021	1,750,000.00	
2022	1,800,000.00	
2023	1,800,000.🔾	
2024	1,850,000.0	
2025	1,850,000.00	